



CHENNAI METRO RAIL LIMITED

CHENNAI METRO RAIL PROJECT PHASE-I- EXTENSION

CONTRACT UAA-08

**“DESIGN VALIDATION AND CONSTRUCTION
OF UNDERGROUND STATION BOXES DWALL
AT SIR THIYAGARAYA COLLEGE &
KORUKKUPET STATION, INCLUDING
ASSOCIATED CUT- COVER AND BORED TBM
TUNNELS”**

ADDENDUM-1



Amendments in tender documents		
Sl.No.	Existing	Amendment
	<i>Tender Document</i>	<i>Replace with</i>
1.	Part-1: Bidding Procedures	Part-1 (Revised) : Bidding Procedures
2.	Part-2: Employer's Requirements	Part-2 (Revised): Employer's Requirements
3.	Part-3: General and Particular Conditions	Part-3 (Revised): General and Particular Conditions

CONTRACT NO. PHASE-I EXTENSION
UAA-08 "Design Validation and Construction of works of underground station Boxes D-Wall at Sir Thiyagaraya College (CH:1016.000m) & Korrukupet (CH:2035.000m) Station, Including Associated Cut-Cover And Bored TBM Tunnels"

PREBID QUERIES

S.NO	Date of Query	Page/ Vol No	Clause No	As in Tender Document	Query	Response by CMRL	Addendum
1	1st Set Prebid Queries dated 6th January, 2016	PART-1, IFB-2	ITB 21.1 Value of EMD	The amount and currency of the Bid Security shall be — INR 8.08 cr. (Rupees Seven Crores Thirty Lakh only) / 1,220,080 USD (One Million Twenty Two Thousands Eighty dollars only) by way of Bank Guarantee/ Bank Demand Draft.	The amount and currency of the Bid Security shall be — INR 8.08 cr. (Rupees Eight Crore Eight Lakhs only) / 1,220,080 USD (One Million Twenty Two Thousands Eighty dollars only) by way of Bank Guarantee/ Bank Demand Draft. Please Clarify	The amount and currency of the Bid Security shall be — INR 8.08 cr. (Rupees Eight Crore Eight Lakhs only) by way of Bank Guarantee/ Bank Demand Draft. This will be corrected in the addendum.	Yes
2	1st Set Prebid Queries dated 6th January, 2016	PART-1, SECTION III, EQC-11	2.4.2 (a) Specific Experience	A minimum number of two similar (i) contracts that have been completed as a prime contractor since 1st January 2005 of which one contract must have been satisfactorily and substantially (ii) completed since 1st January 2010 till the Bid submission deadline.	Request you to modify the clause as 'A minimum number of two similar (i) contracts that have been completed as a prime contractor (single entity or JV member) since 1st January 2005 of which one contract must have been satisfactorily and substantially (ii) completed since 1st January 2010 till the Bid submission deadline.	Not Agreed, Original contract condition Prevails	No
3	1st Set Prebid Queries dated 6th January, 2016	PART-1, SECTION III, EQC-11	2.4.2 (b) Specific Experience	i) Bored TBM Tunnelling of 3 KM	Request you to modify the clause as i) Bored TBM Tunnelling of 2.5 KM	Agreed. Refer Addendum	Yes
4	1st Set Prebid Queries dated 6th January, 2016	PART-1, SECTION III, EQC-12	2.4 Experience Notes for the Bidder	(i) The similarity shall be based on the physical size, complexity, methods/technology and/or other characteristics described in Section VI, Employer's Requirements. Summation of number of small value Contracts (less than the value specified under requirement) to meet the overall requirement will not be accepted. Single similar works mean the construction of Metro Rail underground stations and Tunnels in an urban environment and the minimum value of work should be INR 475 crores.	Request you to modify the clause as Single similar works mean the construction of Metro Rail underground stations and Tunnels in an urban environment and the minimum value of work should be INR 475 crores.	Refer Addendum	Yes
5	1st Set Prebid Queries dated 6th January, 2016	PART-1, SECTION III, EQC-12	2.4 Experience Notes for the Bidder	(ii) Substantial completion shall be based on 80% or more works completed under the Contract.	Request you to modify the clause as (ii) Substantial completion shall be based on Completed value of the Ongoing project of minimum value INR 475 Crores or above.	Refer Addendum	Yes
6	1st Set Prebid Queries dated 6th January, 2016	PART-1, SECTION III, EQC-12	2.4 Experience Notes for the Bidder	Single similar works mean the construction of Metro Rail underground stations and Tunnels in an urban environment and the minimum value of work should be INR 475 crores.	We understand Tunnel means Tunnel Executed by either C&C or TBM or NATM will be acceptable. Please confirm.	Only experience in Bored tunnel using TBM along with cross passage will be considered.	No
7	1st Set Prebid Queries dated 6th January, 2016	PART-1, SECTION IV, BF-10	1.1.2, Retention of Payment for D-wall works in Station boxes	To verify the quality of construction to be as per contractual requirements 10% of the total value of works will be held with the Employer and will only be released once the excavation contractor had excavated the station. In case the D-Wall construction is found to be defective the tenderer has to repair/rectify/replace to the Employers satisfaction, then only this retention money will be released.	Request you not to deduct any retention money as there is no fix timing known when the excavation contractor will finish the work.	Please refer to revised tender documents	Yes
8	1st Set Prebid Queries dated 6th January, 2016	PART-1, SECTION IV, BF-11	1.1.3, Post completion maintenance of bored tunnel works	The tenderer has an obligation to maintain the tunnel lighting, ventilation and dewatering measures as per the Employer's instruction till the mobilisation of new contractor. The employer will pay as per actual the cost incurred by the tenderer.	The tenderer has an obligation to maintain the tunnel lighting, ventilation and dewatering measures as per the Employe employer will pay as per actual the cost incurred plus the cost incurred plus reasonable overhead, profit by the tenderer.	Not Agreed.	No
9	1st Set Prebid Queries dated 6th January, 2016	PART-2, VOLUME-1, SECTION B, B-1	B2		We understand Plunge columns and Diaphragm wall of entrance structure are not in present contract. Please confirm.	Yes, Plunge columns and Diaphragm wall of entrance structure are not in the scope present contract.	No
10	1st Set Prebid Queries dated 6th January, 2016	PART-2, VOLUME 3, SECTION-1, 1-120	Cut and cover Tunnel Employers requirement, scope	Subject line says scope of work includes Associated Cut-Cover Tunnel.	Cross section drawings, BOQ and other details of C&C Tunnel are missing in tender documents. We understand the same is not in present scope of work. Please confirm.	After completion of tunnel boring, cut and cover tunnel will be built in the launching shaft area.	No
11	1st Set Prebid Queries dated 6th January, 2016		Diaphragm wall BOQ	Depth of diaphragm wall not mentioned	Request you to let us know the depth of diaphragm wall.	refer to drawings already provided.	No

CONTRACT NO. PHASE-I EXTENSION
UAA-08 "Design Validation and Construction of works of underground station Boxes D-Wall at Sir Thiyagaraya College (CH:1016.000m) & Korrukupet (CH:2035.000m) Station, Including Associated Cut-Cover And Bored TBM Tunnels"

PREBID QUERIES

S.NO	Date of Query	Page/ Vol No	Clause No	As in Tender Document	Query	Response by CMRL	Addendum
12	1st Set Prebid Queries dated 6th January, 2016		Tunnel segment		Request you to provide typical segment details like concrete, reinforcement, bolts, EPDM/Hydrophil strip details etc	refer to drawings already provided.	No
13	1st Set Prebid Queries dated 6th January, 2016		Land for casting yard	Details not provided.	We request employer to provide us land for casting yard and construction depot free of cost.	Contractor needs to identify the land and factor the price in his bid. In case CMRL provides the land at a later date it will be on monthly payment basis, and the contractor is free to accept or reject the offer.	No
14	1st Set Prebid Queries dated 6th January, 2016		TBM retrieval shaft.		Please let us know if client has identified location of Retrieval shaft.	The location of retrieval shaft has already been shown in Korukpet station drawings. Refer provided drawings.	No
15	1st Set Prebid Queries dated 6th January, 2016		Interface requirement		Please let us know if there is any interface requirement with station balance work contractor.	Yes	No
16	1st Set Prebid Queries dated 6th January, 2016		Back fill		Please let us know if backfilling of launching and retrieval shaft is in scope of work.	Backfilling of launching shaft is in the scope of the contractor, whereas the retrieval shaft needs to be left as is with the earth retention system in place.	No
17	1st Set Prebid Queries dated 6th January, 2016		Key dates	Key date 10: Complete of project is 750 days [25months], however in NIT contract duration given is 20 months	Please let us know the duration of project 25 months or 20 months.	Please refer addendum.	Yes
18	1st Set Prebid Queries dated 6th January, 2016		Design & AutoCAD Drawings	PDF drawings are provided with tender documents	Request you to provide soft copy of tender documents in AUTOCAD format.	Cad copies will not be provided.	NO
19	1st Set Prebid Queries dated 6th January, 2016		Due date of submission	Due date of submission is on 04.02.2016	We are in the process of preparing technical responsive and competitive offer. Request you to extend the due date till 04-03-2016.	Date extended upto 11-02-2016. Please refer addendum.	Yes
21	2nd Set Prebid Queries dated 12th January, 2016		Volume-1 section —B scope of works B2 (vii) Validation of the D-wall of two stations at Thiyagaraya college and Korrukupet stations		Please clarify the scope under validation of designs, Who will be responsible for the Design of diaphragm walls and their structural adequacy and safety. Although in Volume-1 section C-2 it gives some description, all functions mentioned thereby is generally the scope of client's DDC. How can a contractor have this validated? What happens in case the designs are changed to a great extent thereby affecting the cost to contractor?? CMRL may appoint a separate proof checking agency in this regard or better option would be to go for design and built type contract as previously done	The DDC is responsible for Design of Permanent works.	No
22	2nd Set Prebid Queries dated 12th January, 2016		Volume-1, section —B scope of works B2 (vii) Validation of the D-wall of two		Please Confirm Whether all couplers etc required at various slab levels needs to be checked by contractor's designer independently??	The DDC is responsible for Design of Permanent works.	No
23	2nd Set Prebid Queries dated 12th January, 2016		Volume-1 section —B scope of works B2 (vii) Validation of the D-wall of two		We presume that the extent and height of Diaphragm walls, the provided reinforcement in D-walls for crack width control etc will be provided by the DDC of CMRL	Yes.	No
24	2nd Set Prebid Queries dated 12th January, 2016		Volume-1 section —B scope of works B2 (vii) Validation of the D-wall of two		D-wall design and construction is intimately linked with temporary stage bracings , slabs etc. Please Confirm.	DDC is responsible.	No
25	2nd Set Prebid Queries dated 12th January,		Volume-1 section —B5	The design life of permanent works 120 years	Please clarify how the contractor will validate this statement.	The contractor has to comply with employers requirement, technical and construction specification, quality control standards, and he has to build as per design drawings/specification.	No

CONTRACT NO. PHASE-I EXTENSION
UAA-08 "Design Validation and Construction of works of underground station Boxes D-Wall at Sir Thiyagaraya College (CH:1016.000m) & Korrukupet (CH:2035.000m) Station, Including Associated Cut-Cover And Bored TBM Tunnels"

PREBID QUERIES

S.NO	Date of Query	Page/ Vol No	Clause No	As in Tender Document	Query	Response by CMRL	Addendum
26	2nd Set Prebid Queries dated 12th January,				During Site Visit, we we went to see the location for Thiyagaraya College Station. The Principal of the Institution did not allow us for the same. Please confirm whether all permissions are in place.	Site will be handed over to the contractors progresssely.	
27	2nd Set Prebid Queries dated 12th January, 2016				During Site Visit, we found that there will be demolition of existing houses and buildings which will be required for construction of D-wall. Please confirm that hindrance free ROW will be handed over to us as per schedule.	Demolation of Existing Structure in the work area boundary is the responsibility of the constructor.	No
28	2nd Set Prebid Queries dated 12th January,		Diaphragm wall Design		Please confirm Diaphragm wall is designed for Top — Down construction or Bottom-Up Construction for Stations.	Top-Down Construction only for both stations except for Kurukpet station rettieval shaft area.	No
29	2nd Set Prebid Queries dated 12th January,		Traffic Diversion Plan		Please provide us with approved Traffic Diversion plan for this project.	This is the responsibility of the contractor	No
30	3rd Set Prebid Queries dated 15th January	Thiyagaraya College			During Site Visit, we went to see the location for Thiyagaraya College Station. The Principal of the Institution did not allow us for the same. Please confirm hindrance free access to take all construction equipment and other resources will be provided by CMRL.	Refer to addendum, land will handed over progressively	Yes
31	3rd Set Prebid Queries dated 15th January	Cut and cover Tunnel at Launching shaft	BOQ Table-3, Page BF-39	Pre-bid meeting and reply to bidders query-1	As per reply to bidders query Sr. no. 1- The launching shaft at Washermanpet station has to be built by cut and cover technique and backfilled after completion of works. Quantity for C&C Tunnel is not included in Table no.-3 of BOQ. Kindly provide quantity for C&C Tunnel.	It is included in the bored tunnel quantities	No
32	3rd Set Prebid Queries dated 15th January	Bill of Quantities	BOQ Table-3, Page BF-40, Item 4.10	Quantity for RCC base slab is missing	Request you to provide us unit and Quantity for RCC base.	Refer to Addendum	Yes
33	3rd Set Prebid Queries dated 15th January	Bill of Quantities	BOQ Table-1, BOQ Table-3	BOQ Table-1: Diaphragm wall quantity for Thiyagaraya Station given is 12,000 m3 (1m thick), where as in Table-2: Diaphragm wall quantity for Thiyagaraya Station given is 11,043 Sqm	Please let me know if we have to price for 11,043 Sqm or 12,000 Sqm Diaphragm wall quantity for Thiyagaraya Station.	Refer to Addendum	Yes
34	3rd Set Prebid Queries dated 15th January	Bill of Quantities	BOQ Table-1, BOQ Table-3	BOQ Table-1: Diaphragm wall quantity for Kurrukkopet Station given is 10,000 m3 (1m thick),	Please let me know if we have to price for 10,000 Sqm or 9,535 Sqm Diaphragm wall quantity for Kurrukkopet Station.	Refer to Addendum	Yes
35	3rd Set Prebid Queries dated 15th January			where as in Table-2: Diaphragm wall quantity for Kurrukkopet Station given is 9,535 Sqm		Refer to Addendum	Yes
36	3rd Set Prebid Queries dated 15th January	Bill of Quantities	BOQ Table-3, Item 3.10, Pg. BF-41	Table-2: quantity for Excavation till formation level given is 9,571 and unit mentioned is Item.	We presume unit for excavation in BOQ item no. 3.10 is cum instead of Item. Please confirm.	Refer to Addendum	Yes
37	3rd Set Prebid Queries dated 15th January	GFRP	Drawings of GFRP and reinforcement	The BOQ shows 16mm, 20mm, 25mm, 32m GRFP bars. However Drawings shows only 16mm and 40mm GRFP bars	There is mismatch between what is shown on drawings and what is given in BOQ for GRFP bars. Request you to clarify.	Refer to Addendum	Yes
38	1st Set Prebid Queries dated 11th January	IFB-2/part 1, Invitation for Bids	Point No 6 Bid Submission	Bids must be delivered to the address above on or before 14.00 Hrs 1ST on 04-02-2016	Request to extend submission date at least 6 weeks from 04.02.2016.	Date extended upto 11-02-2016. Please refer addendum.	Yes
39	1st Set Prebid Queries dated 11th January	SIB-2	Clause 45.1.1 Initial Filter	Design Validation Form	Kindly provide the format for Design Validation form.	It is a design validation certificate, the format is provided.	No
40	1st Set Prebid Queries dated 11th January	SIB-6	Clause 45.4.2	All the Contractors plants and equipment are required to be certified by competent authority/organization periodically as per statutory requirements. Necessary insurance for the equipment's and third party insurance also should be covered by the Bidder during the period of usage.	As the project duration is stringent (2 years (approx.), any delay in certification from competent authority would hamper the Project works. Hence, this clause could be deleted. Please Clarify	Not Acceptable	No

CONTRACT NO. PHASE-I EXTENSION
UAA-08 "Design Validation and Construction of works of underground station Boxes D-Wall at Sir Thiyagaraya College (CH:1016.000m) & Korrukupet (CH:2035.000m) Station, Including Associated Cut-Cover And Bored TBM Tunnels"

PREBID QUERIES

S.NO	Date of Query	Page/ Vol No	Clause No	As in Tender Document	Query	Response by CMRL	Addendum
41	1st Set Prebid Queries dated 11th January	EQC-2/Part 1, Section III, EC & QR Initial	1.1.2 P&M		As there is very less excavation work 4 nos of excavators, 2 nos of Cranes, 2 nos of loaders are not required. Please Confirm.	Given the construction schedule, infact we have double the required in the revised documents.	No
42	1st Set Prebid Queries dated 11th January	EQC-11/Part 1, Section III, EC & QR Initial Filter	2.4.2(b) Specific Experience		To evaluate the contractors completed jobs, the price level assuming 5% inflation for Indian rupees every year and 2% for foreign currency portions per year should be added in the total Contract Value. Please Confirm.	Not Agreed	No
43	1st Set Prebid Queries dated 11th January	BDS-3	ITB 21.1 Bid Security	The amount and currency of the Bid security shall be INR 8.08 cr (Rupees Seven Crores Thirty lakh only)....	There seems to be some error in the Bid security value in number and words. Please Clarify	The amount and currency of the Bid Security shall be — INR 8.08 cr. (Rupees Eight Crore Eight Lakhs only) by way of Bank Guarantee/ Bank Demand Draft. This is corrected in the addendum.	Yes
44	1st Set Prebid Queries dated 11th January	BDS-3	ITB 21.1 Bid Security	The amount and currency of the Bid security shall be INR 8.08 cr (Rupees Seven Crores Thirty lakh only)....	There seems to be some error in the conversion of INR 8.08 Cr. to 1.22 Million USD. Kindly Clarify.	The amount and currency of the Bid Security shall be — INR 8.08 cr. (Rupees Eight Crore Eight Lakhs only) by way of Bank Guarantee/ Bank Demand Draft. This is corrected in the addendum.	Yes
45	1st Set Prebid Queries dated 11th January	BF-8/part 1, Section IV Bidding Forms	Schedule of Adjustmen t Data (C) Source	RBI-CPI- (labour)	Request to consider minimum wages as per Govt. of Tamil Nadu.	Not Agreed.	No
46	1st Set Prebid Queries dated 11th January	BF-8/part 1, Section IV Bidding Forms	Schedule of Adjustmen t Data (C) Source	RBI-CPI - Cement	Request to please change to WPI indices.	Please refer addendum.	Yes
47	1st Set Prebid Queries dated 11th January	BF-8/part 1, Section IV Bidding Forms	Schedule of Adjustmen t Data (C) Source of Index	RBI-CPI - Steel	Request to please change to WPI indices.	Please refer addendum.	Yes
48	1st Set Prebid Queries dated 11th January	BF-8/part 1, Section IV Biddingt Forms	Schedule of Adjustmen Data (C) Source of Index	RBI-CPI- Fuel	Request to please consider IOCL price.	Please refer addendum.	Yes
49	1st Set Prebid Queries dated	BF-8/Part 1/Section IV	Bidding Forms Schedule of	Bidder's proposed Weighting a : 0.3(Fixed)	Usually it is 0.15, Request to change to 0.15(Fixed) instead of 0.3(Fixed).	Not Agreed	No
50	1st Set Prebid Queries dated 11th January	BF-8/Part 1/Section IV Bidding Forms	Clause 1.1.2 Retention of Payment for works in	D-wall	As there is 10%of D wall works as retention, request to please confirm the schedule of excavation contractor and details of excavation contractors.	Please refer addendum for details.	Yes
51	1st Set Prebid Queries dated 11th January	BF-39/Part 1/Section IV Bidding Forms	Base line quantities	Request to provide the relation between Baseline	quantities in Table 3 with Tender price.	Already Explained in the prebid meeting refer Addendum	Yes
52	1st Set Prebid Queries dated 11th January	GC-5.1/Part 3, Section VII, General Conditions	Clause 5.1 General Design Obligations	The DDC for the work will supply all Good for Construction Drawings to the Contractor from time to time as per construction schedule. Based on the GFC drawings the contractor has to prepare Shop drawings. The Design validation of DDC's drawings based on the constructability point of view has to be considered by the contractor and any changes if required has to be notified to the DDC, who will change the drawing accordingly.	in case of any delay in providing drawings by DDC, then the Contractor shall be suitably compensated in time and cost. Please Clarify.	The design will be available as per the construction scheudle, in the event of any delay it will be discussed on case to case basis.	No

CONTRACT NO. PHASE-I EXTENSION
UAA-08 "Design Validation and Construction of works of underground station Boxes D-Wall at Sir Thiyagaraya College (CH:1016.000m) & Korrukupet (CH:2035.000m) Station, Including Associated Cut-Cover And Bored TBM Tunnels"

PREBID QUERIES

S.NO	Date of Query	Page/ Vol No	Clause No	As in Tender Document	Query	Response by CMRL	Addendum
53	1st Set Prebid Queries dated 11th January	GC-14/Part 3, Section VII, General Conditions	Clause 2.2 Permits, Licenses or Approvals	The Employer shall provide, at the request of the Contractor, such reasonable assistance as to allow the Contractor to obtain properly: (a)copies of the Laws of the Country which are relevant to the Contract but are not readily available, and (b)any permits, licences or approvals required by the Laws of the Country: (i)which the Contractor is required to obtain under Sub-Clause 1.13 [Compliance with Laws), (ii)for the delivery of Goods, including clearance through customs, and (iii)for the export of Contractor's Equipment when it is removed from the Site.	Please confirm that any delays as a result of obtaining approvals/permits/licences from any authorities that are beyond the control of the Contractor shall not be considered as non-performance.	Not Agreed.	No
54	1st Set Prebid Queries dated 11th January	GC-78/Part 3, Section VII, General Conditions	Clause 20.2 Appointment of the Dispute Board	The terms of the remuneration of either the sole member or each of the three members, including the remuneration of any expert whom the DB consults, shall be mutually agreed upon by the Parties when agreeing the terms of appointment. Each Party shall be responsible for paying one half of this remuneration.	Kindly Provide the remuneration details to be provided to the members of Dispute Board.	It will be decided at the time of appointment.	No
55	1st Set Prebid Queries dated 11th January	GC-24/Part 3, Section VII, General Conditions	Clause 4.15 Access Route	The Contractor shall be deemed to have satisfied himself as to the suitability and availability of the access routes he chooses to use..... The Employer will not be responsible for any claims which may arise from the use or otherwise of any access route. The Employer does not guarantee the suitability if availability of any particular access route,	Request to consider compensation in case of delays caused due to non-availability of continuous access.	Not Acceptable	No
56	1st Set Prebid Queries dated 11th January	GC-25/Part 3, Section V11, General Conditions	Clause 4.18 Protection of Environment	The Contractor shall take all reasonable steps to protect the environment (both on and off the Site) and to limit damage and nuisance to people and property resulting from pollution, noise and other results of his operations. The Contractor shall ensure that emissions, surface discharges and effluent from the Contractor's activities shall not exceed the values indicated in the Employer's Requirements or prescribed by applicable Laws.	Protection of the environment shall be limited to within Site premises only as the Contractor could not be held responsible for Environmental impacts in outside the site locations. Please modify the clause accordingly.	Not Acceptable	No
57	1st Set Prebid Queries dated 11th January	GC-26/Part 3, Section VII, General Conditions	Clause 4.22 Security of the site	Unless otherwise stated in the Particular Conditions: (a)the Contractor shall be responsible for keeping unauthorised persons off the Site, and (b)authorised persons shall be limited to the Contractor's Personnel and the Employer's Personnel; and to any other personnel notified to the Contractor, by the Employer or the Engineer, as authorised personnel of the Employer's other contractors on the Site.	Request to consider sharing of various cost incurred by civil contractor in case of services used by designated system wide contractor.	Not Acceptable as management of interface with others is contractors responsibility	No

CONTRACT NO. PHASE-I EXTENSION
UAA-08 "Design Validation and Construction of works of underground station Boxes D-Wall at Sir Thiyagaraya College (CH:1016.000m) & Korrukupet (CH:2035.000m) Station, Including Associated Cut-Cover And Bored TBM Tunnels"

PREBID QUERIES

S.NO	Date of Query	Page/ Vol No	Clause No	As in Tender Document	Query	Response by CMRL	Addendum
58	1st Set Prebid Queries dated 11th January	GC-39/ Part-3, Section VII, General Condition	Clause No. 8.4, Extension of Time for Completion	The Contractor shall be entitled subject to Sub-Clause 20.1 [Contractor's Claims] to an extension of the Time for Completion if and to the extent that completion for the purposes of Sub-Clause 10.1 [Taking Over of the Works and Sections] is or will be delayed by any of the following causes: (a) a Variation (unless an adjustment to the Time for Completion has been agreed under Sub-Clause 13.3 [Variation Procedure]), (b) a cause of delay giving an entitlement to extension of time under a Sub-Clause of these Conditions, (c) exceptionally adverse climatic conditions, (d) Unforeseeable shortages in the availability of personnel or Goods caused by epidemic or governmental actions, or (e) any delay, impediment or prevention caused by or attributable to the Employer, the Employer's Personnel, or the Employer's other contractors. If the Contractor considers himself to be entitled to an extension of the Time for Completion, the Contractor shall give notice to the Engineer in accordance with Sub-Clause 20.1 [Contractor's Claims]. When determining each extension of time under Sub-Clause 20.1, the Engineer shall review previous determinations and may increase, but shall not decrease, the total extension of time.	There is provision only for compensation of time and not cost. The Contractor should be compensated for costs arising due to delays not attributable to the Contractor.	Not agreed	No
59	1st Set Prebid Queries dated 11th January	GC-59/Part 3, Section VII, General Conditions	Clause 14.7 Payment	(b) the amount certified in each Interim Payment Certificate within 56 days after the Engineer receives the Statement and supporting documents or, at a time when the Bank's loan or credit (from which part of the payments to the Contractor is being made) is suspended, the amount shown on any statement submitted by the Contractor, within 14 days after such statement is submitted, any discrepancy being rectified in the next payment to the Contractor including any amounts due in accordance with a decision by the DB which have been included in the Interim Payment Certificate; and	We request to consider payment of 80% of the interim amount within 7 days from the date of submission of monthly invoice and the balance 20% in next 14 days.	Not Agreed, However efforts will be made to release the payment as soon as possible in the interest of the work.	No
60	1st Set Prebid Queries dated 11th January	GC-73/Part 3, Section VII, General Conditions	Clause 18.3 Insurance against injury to Persons and Damage to Property	The insuring Party shall insure against each Party's liability for any loss, damage, death or bodily injury which may occur to any physical property (except things insured under Sub-Clause 18.2 [Insurance for Works and Contractor's Equipment]) or to any person (except persons insured under Sub-Clause 18.4 [Insurance for Contractor's Personnel]), which may arise out of the Contractor's performance of the Contract and occurring before the issue of the Performance Certificate. This insurance shall be for a limit per occurrence of not less than the amount stated in the Contract Data, with no limit on the number of occurrences. If an amount is not stated in the Contract Data, this Sub-Clause shall not apply. As per Particular Conditions(PC) Part A — Contract Data Minimum amount of Third Party Insurance — INR 0.50 Million INR per occurrence.	Please consider having limitation for the number of incidents (say 4 nos.). For any further incidences, then the same shall be suitably compensated by the Employer.	Not Acceptable	No
61	1st Set Prebid Queries dated 11th January	1-3/Part 3, Section VIII, Particular	Time for Completion	720 days	Considering the quantum of work involved - Bidder requests to increase the project duration from 720 days to 900 days.	Not agreed	No

CONTRACT NO. PHASE-I EXTENSION
UAA-08 "Design Validation and Construction of works of underground station Boxes D-Wall at Sir Thiyagaraya College (CH:1016.000m) & Korrukupet (CH:2035.000m) Station, Including Associated Cut-Cover And Bored TBM Tunnels"

PREBID QUERIES

S.NO	Date of Query	Page/ Vol No	Clause No	As in Tender Document	Query	Response by CMRL	Addendum
62	1st Set Prebid Queries dated 11th January	1-3/Part 3, Section VIII, Particular	Defects Notification Period	730 days	Request to reduce the DLP to 1 year.(I.e.365 days) , <i>P A A A Y F 11)</i>	Not Agreed	No
63	1st Set Prebid Queries dated 11th January	1-3/Part 3, Section VIII, Particular Conditions/P C-3	Performance Security	"The Performance Security will be in the form of a "demand guarantee" or "performance bond" in the amount(s) of 7.5%percent of the Accepted Contract Amount and in the same currency(ies) of the Accepted Contract Amount.	Request to reduce the Performance Security 7.5% to 5%	Not Agreed	No
64	1st Set Prebid Queries dated 11th January	1-4/Part 3, Section VIII, Particular Conditions/P	Maximum amount of Delay damages	10%	Request to limit to maximum 5% instead of	Not Acceptable	No
65	1st Set Prebid Queries dated 11th January	1-4/Part 3, Section VIII, Particular	Plant and Materials	Deleted	Request to provide 10% interest free P&M	Not Acceptable	No
66	1st Set Prebid Queries dated 11th January	1-4/Part 3, Section VIII, Particular	Minimum Amount of Interim Payment	2% of the Accepted Contract Amount	Request to delete this clause and it should actuals.	Please refer to Addendum	Yes
67	1st Set Prebid Queries dated 11th January	1-5/Part 3, Section VIII, Particular Conditions/P	Periods for submission of insurance	14 days from issue of LOA	Request to increase to 30 days from issue instead of 14 days	please refer addendum	Yes
68	1st Set Prebid Queries dated 11th January	2-5/ Part 3, Section VIII, Part B - Specific Provisions	SP 10 4.10 Site Data	4.10.1The responsibility of the Contractor under sub-clause 4.10 of GC is full arid final and no claim by the Contractor for additional payment or extension of time shall be allowed on the grounds that of any misunderstanding or misapprehension by the Contractor or that incorrect or insufficient information was given to the Contractor or that he failed to obtain correct and sufficient information.	Request to consider extension of time as well as cost control compensation since it is beyond Contractor's	Not Agreed.	No
69	1st Set Prebid Queries dated 11th January	2-5/ Part 3, Section VIII, Particular conditions/P C-5	LD	All Key Dates		Please refer addendum	Yes
							Yes
							Yes
70	1st Set Prebid Queries dated 11th January	2-17,Part 3, Section VIII Part B Particular Conditions	SP 26 2.1 Right of Access to the site	In case of delay in handing over of the site by the Employer, the Contractor will be given extension of time only. The payment in the extended period in such cases will be price adjustment effective from the original date of completion.	Only time compensation is available in case of any to provide delay in Right of Access to Site. Request cost compensation also.	Not Agreed	No
71	1st Set Prebid Queries dated 11th January	2-5/,Part 3, Section VIII Part B Particular Conditions	SP 13 4.16 Transport of Goods	No extra payment will be made for construction and maintenance of temporary haul roads if any needed including any special protection or strengthening required and all cost of such works shall be deemed to have been included in the costs of items contained in the Pricing Documents.	Only the temporary haul roads near to the Project Site are considered under this clause. If it is beyond, then the Contractor should not be held responsible. Please Clarify and also provide : (i) the details of roads which would come under the purview of this Clause shall be provided by Client (ii) Whether the payment for this item as per separate BOQ or to be included in Lumpsum Price?	Not Agreed	No

CONTRACT NO. PHASE-I EXTENSION
UAA-08 "Design Validation and Construction of works of underground station Boxes D-Wall at Sir Thiyagaraya College (CH:1016.000m) & Korrukupet (CH:2035.000m) Station, Including Associated Cut-Cover And Bored TBM Tunnels"

PREBID QUERIES

S.NO	Date of Query	Page/ Vol No	Clause No	As in Tender Document	Query	Response by CMRL	Addendum
72	1st Set Prebid Queries dated 11th January	2-8/,Part 3, Part 13 Particular Conditions	Section VIII ^{8.5} SP 17 Delays caused by Authorities	iii)Weather conditions, unless they constitute a 50 year recurrence interval which adversely affect the progress of the Works, or x)Any interference from third parties illegally interfering with the Site, access to and from the Site or with works areas, camps, storage, offices or facilities, or xi)An instruction by the Employer's Representative to revise the Quality Plan or the Safety Plan pursuant to GC Clause 4.8 or GC Clause 6.7 respectively, or	The Contractor shall not be held responsible for any interference due to Weather conditions, third parties and Employer.	Not Agreed	No
73	1st Set Prebid Queries dated 11th January	2-10/,Part 3, Section VIII Part 8 Particular Conditions	SP 21 13.7 Adjustment for changes in legislation	If the Price Variation Formula in SP Clause 22 below is adopted by the Contractor, then no addition or reduction in cost due to any Changes in Law will be allowed, except for changes to i) Customs Duties and ii) Excise Duties, iii) Output TN VAT which shall be to the Employer's account, to the extent that it is not covered by the Price Variation Formula.	As imposition of GST is imminent, the above mentioned clause is ambiguous and not clear as per our experience with our earlier CMRL package. Please Clarify	Please refer to SP21, Cl. 13.7.2.	No
74	1st Set Prebid Queries dated 11th January	2-12/,Part 3, Section VIII Part B Particular Conditions	SP 22 13.8 price Variation Formula		In case of approved extended stay, whether the Contractor shall be suitably compensated as per the prevailing indices rather than restricting to or comparing with indices as on Original Contract period. Please Clarify.	Not Agreed	No
75	1st Set Prebid Queries dated 11th January	Part - 2 - Section VI - Volume -3,	Drawing No. DDC101-PD- US1-AR-DW-15201-AI		The chainage for korukkupet station shows CH: 2035.00 whereas DWG NO: DDC101-PD-TUN-AL-DW-13037-AI shows 1977.50 please clarify	Please refer addendum.	Yes
76	1st Set Prebid Queries dated 11th January	Part - 2 - Section VI - Volume -3,	Drawing No. DDC101-PD-US1-AR-DW-15104-AI		The chainage for Thiyagaraya station shows CH: 1011.00 whereas whereas DWG NO: DDC101-PD-TUN-AL-DW-13036-AI shows 1020.00 please clarify	Please refer addendum.	Yes
77	1st Set Prebid Queries dated 11th January	Part - 2 - Section VI - Volume -3,	DDC101-PD- TUN-AL- D W-13038- A I		Ending chainage 2735.15 m given in (Dwg No. DDC101-PD-TUN-AL-DW-13038-A1) is not matching with ending chainage 2732.32 m given in tunnel and station (Dwg No.DDC101-PD-TUN-OW-DW-13728-A1) kindly clarify.	Please refer addendum.	Yes
78	1st Set Prebid Queries dated 11th January	Part - 2 - Section VI - Volume -3,			Request to provide AutoCAD drawings for tender document (Part - 2 - Section VI - Volume -3, can be provided	Not Agreed	No
79	1st Set Prebid Queries dated 11th January	Part - 2 - Section VI - Volume -3,	DDC101-PD-US1-AR-DW- 15210		The clear vertical clearance in concourse area is shown as 5.1 m in (DWG: DDC101-PD-US1-AR-DW-15210 & 15110) but it is shown as 5.2m in(DWG: DDC101-PD-US1-ST-DW-15407 & 15607) please clarify	The differnece is due to finishing requirements.	No
80	1st Set Prebid Queries dated 11th January	Part - 2 - Section VI - Volume -3,	DDC101-PD- US1-AR-DW- 15210		The concourse, platform and undercroft level in (DWG: DDC101-PD-US1-AR-DW-15210) and (DWG: DDC101-PD-US1-ST-DW-15607) does not match please clarify	The differnece is due to finishing requirements.	No
81	1st Set Prebid Queries dated 11th January	Part - 2 - Section VI - Volume -3,	DDC101-PD- US1-AR-DW- 15110		The concourse, platform and undercroft level in (DWG: DDC101-PD-US1-AR-DW-15110) and (DWG: DDC101- PD-US1-ST-DW-15407) does not match please clarify	The differnece is due to finishing requirements.	No
82	1st Set Prebid Queries dated 11th January	Part - 2 - Section VI - Volume 3,	DDC101-PD-US1-AR-OW- 15102		In the Drawings DDC101-PD-US1-AR-DW-15102 DDC101-PD-US1-AR-DW-15110 the legend table which gives abbreviation of different components and sizes is not provided.	Refer to Addendum	Yes
83	1st Set Prebid Queries dated 11th January	- - Part 2 Section VI - Volume -3,	DDC101-PD-US1-AR-DW-15201		In the Drawings DDC101-PD-US1-AR-DW-15201 DDC101-PD-US1-AR-DW-15210 the legend table which gives abbreviation of different components and sizes is not provided.	Refer to Addendum	Yes
84	1st Set Prebid Queries dated 11th January	Part - 2 - Section VI - Volume -3,	DDC101-PD- US1-ST-DW- 15402		Columns dimensions are not provided in (DWG NO : DDC101-PD-US1-ST-DW-15602 & DDC101-PD-US1-ST-DW-15402)	It is not in the scope of this contract.	No

CONTRACT NO. PHASE-I EXTENSION
UAA-08 "Design Validation and Construction of works of underground station Boxes D-Wall at Sir Thiyagaraya College (CH:1016.000m) & Korrukupet (CH:2035.000m) Station, Including Associated Cut-Cover And Bored TBM Tunnels"

PREBID QUERIES

S.NO	Date of Query	Page/ Vol No	Clause No	As in Tender Document	Query	Response by CMRL	Addendum
85	1st Set Prebid Queries dated 11th January	Part - 2 - Section VI - Volume - 3,	DDC101-PD-US2-ST-DW-	15661	D-WALL Toe level not given in DWG NO : DDC101-PD-US2-ST-DW-15661 & DDC101-PD-US2-ST-DW-15461	Please refer the cross section A-A of respective station.	No
86	1st Set Prebid Queries dated 11th January	Part — II	Geo- Technical		Provided 5 bore holes is not sufficient to validate the design.	A seismic refraction survey report has already been provided along with bore holes data to the tenderers for help. However, additional available borehole datas will be provided through addendum.	No
87	1st Set Prebid Queries dated 11th January	General	Cross Passage		Ground Improvement at cross passage location is not defined in the drawings. It is mentioned to suit ground condition. Provide ground improvement details for cross passages.	Refer to Drawings, Jet grouting is proposed. However this is part of tempoyary works which is to be designed by the contractor. This proposal has to be approved by Employer's designer.	No
88	1st Set Prebid Queries dated 11th January	Volume 1 — Appendix 22			Provide details for chartered and unchartered utilities.	All the utility related met during the excecution will be paid as per the actuals based on the concerned departmental rates, and as per the utility department requirement.	No
89	1st Set Prebid Queries dated 11th January	2 -	Volume -3' Section VI details		Kindly provide the Ramp details and Drawings.	Not part of this contract.	No
90	1st Set Prebid Queries dated 11th January	General			First stage concreting inside tunnel details is required (in particular cross sectional details).	refer relevant drawing provided with the documents.	No
91	1st Set Prebid Queries dated 11th January		18 Casting Yard & Batching plant	Availability of land will be intimated later a date.	Please provide the most likely location, area details & plot layout of Casting Yard for planning purpose	Contractor needs to identify the land and factor the price in his bid. Incase CMRL provides the land at a later date it will be on monthly payment basis, and the contractor is free to accept or reject the offer.	No
92	1st Set Prebid Queries dated 11th January	D3-Volume 1- Section —D	18 Muck Disposal site	Suitable land for disposal of muck	Please provide the most likely location, area & capacity of the Dumping yard for planning purpose	Refer to appenddum	Yes
93	1st Set Prebid Queries dated 11th January				Kindly provide the maximum height of muck temporary stacking permissible near station locations	On the case to case it will be decided by employer.	No
94	1st Set Prebid Queries dated 11th January	12-1-Volume 1- Appendix- 12	Charted Utilities		Kindly provide the details of chartered utilities to be covered under the scope, also please provide the proposal for the same - 'To be Diverted Temporary / To be Diverted Permanent / To be Supported	All the utility related items met with during the excecution will be paid as per the actuals based on the concerned departmental rates, and as per the utility department requirement.	No
95	1st Set Prebid Queries dated 11th January	2A-1,Volume 1- Appendix 2A	12 Work Area	Schedule of site access details	Please provide the location, area & layout details of land that will be provided for work area pockets for Launching shaft	Refer to addendum	Yes
96	1st Set Prebid Queries dated 11th January	2A-1,Volume 1- Appendix 2A	12 Work Area	Schedule of site access details	Please provide the location, area & layout details of land that will be provided for work area pockets for Thiyagaraya Station	Refer to addendum	Yes
97	1st Set Prebid Queries dated 11th January	2A-1,Volume 1- Appendix 2A	12 Work Area	Schedule of site access details	Please provide the location, area & layout details of land that will be provided for work area pockets for Korrukupet Station.	Refer to addendum	Yes
98	1st Set Prebid Queries dated 11th January	2A-1,Volume 1- Appendix 2A	12 Work Area	Schedule of site access details	Please provide the location, area & layout details of land that will be provided for TBM works	Refer to addendum	Yes
99	1st Set Prebid Queries dated 11th January	2A-1,Volume 1- Appendix 2A	12 Work Area	Schedule of site access details	Please provide the location, area & layout details of land that will be provided as construction depot	Refer to addendum	Yes
100	1st Set Prebid Queries dated 11th January	2B-1,Volume 1 Appendix 2B	Contract Key Dates	KD-4 Construction of TBM Tunnel up to Sir Thiyagaraya College Station	Please clarify whether Key date for TBM refers to completion of first tunnel or second Tunnel completion	Completion of Both	No
101	1st Set Prebid Queries dated 11th January	2B-1,Volume 1 Appendix 2B	Contract Key Dates	KD-6 Construction of TBM Tunnel up to Korrukupet Station	Please clarify whether Key date for TBM refers to completion of first tunnel or second Tunnel completion	Completion of Both	No

CONTRACT NO. PHASE-I EXTENSION
UAA-08 "Design Validation and Construction of works of underground station Boxes D-Wall at Sir Thiyagaraya College (CH:1016.000m) & Korrukupet (CH:2035.000m) Station, Including Associated Cut-Cover And Bored TBM Tunnels"

PREBID QUERIES

S.NO	Date of Query	Page/ Vol No	Clause No	As in Tender Document	Query	Response by CMRL	Addendum
102	1st Set Prebid Queries dated 11th January	Volume 4	Drawings		Drawing Number DDC101-PD-US2-ST-DW-15451: D-wall layout shown does not show the entry exit. We understand that the D-wall for entry exit is not in the scope of the contractor, please confirm.	Yes, D-Wall from entry exit is not in the scope of this tender.	No
103	1st Set Prebid Queries dated 11th January	Volume 4	Drawings		Drawing Number DDC101-PD-U52-ST-DW-15651: D-wall layout shown does not show the entry exit. We understand that the D-wall for entry exit is not in the scope of the contractor, please confirm.	Yes, D-Wall from entry exit is not in the scope of this tender.	No
104	1st Set Prebid Queries dated 11th January	Volume 4	Drawings		Drawing Number DDC101-PD-TUN-ST-DW-13182: Please provide proposed details of Ground improvement & dewatering for pre-bid design validation.	Tempopary ground improvement including dewatering is part of the contractor's design.	No
105	1st Set Prebid Queries dated 11th January	Volume 4	Drawings		Please provide details of existing water well.	It is contractor's responsibility to find out the borewell /open well along the alignment	No
106	1st Set Prebid Queries dated 11th January	B2-Volume 1- Section B	xix Scope of works	Other works as stated in the Employer Requirements outline specifications and Employer's Drawings ,	We understand that this clause does not refer any works in the stations other than D-Wall, under scope of the contractor. Please confirm.	YES.	No
107	1st Set Prebid Queries dated 11th January	Section II,BDS -2	ITA 7.1		Since this design validation is in contractors scope major queries may rise until completion of design validation, hence please accept additional queries till 15 days prior to submission.	We have already extended the prebid queries period till 20th Jan 16.	No
108	1st Set Prebid Queries dated 11th January	General			In Theyagara Station do we have to relaunch the TBM or is it Drive though the station. Kindly Confirm	Drive through the Thiyagaraya station.	No
109	1st Set Prebid Queries dated 11th January	General			What are the schedules of other construction contractors like excavation, slab concrete etc.	The contractor shall take care of this uncertainty in the arrival of the subsequent contractor, however CMRL will endeavour to provide such schedule as soon as possible.	No
110	1st Set Prebid Queries dated 11th January, 2016	(i) PartI , Section -IV (Bidding Forms), CI - 1.1, Preamble , Page : 8F-10 Oil PartI , Section -IV (Bidding Forms), Price Centre B to I, Page: BF-30 to 38		(i)"The total amount of each of the Price Centers B to I shall be equal to 95% of the Sum of the Price Centers inserted into the Pricing Summary in Clause 1.7" (ii)"Price Center "B" to "I" shall be equal 92.5% of the sum inserted for price centre "8" to "1" in the pricing summary in clause 1.7"	There is the ambiguity in the total amount of each of the Price Centers B to I in the stated para. Bidder understand that the total amount of each of the Price Centers B to I shall be equal to 92.5% of the Sum of the Price Centers inserted into the Pricing Summary in Clause 1.7. Please clarify the ambiguity.	Understanding is correct. Please refer addendum.	Yes
111	1st Set Prebid Queries dated 11th January, 2016	PartI , Section -IV (Bidding Forms), CI - 1.1.1 Preamble , Page : BF-10		"The rates should be based on TN PWD schedules rates 2015. For the items not available in TNPWD schedule, DSR 2015 will be adopted. No escalation will be allowed"	Bidder understand that the rates which are not available in TNPWD schedule, the DSR 2015 will be adopted. Since the contract period is of 720 days (24 months) bidder request to allow escalation above the rates arrived from DSR 2015.	Refer to Addendum, it will be paid on current TNPWD or DSR Chennai rates.	Yes
112	1st Set Prebid Queries dated 11th January, 2016	Peril , Section -IV (Bidding Forms), Price Centre for Payments, Price Centre-E Page : BF-33		"Price Centre -0, Diaphragm Wall at Kurukkapet Station"	Bidder understand that there is some typographical error. The Price Centre D, shall be read as Price Centre E. Please confirm.	Yes, Price Centre D shall be read as Price Centre E. Refer addendum.	Yes

CONTRACT NO. PHASE-I EXTENSION
UAA-08 "Design Validation and Construction of works of underground station Boxes D-Wall at Sir Thiyagaraya College (CH:1016.000m) & Korrukupet (CH:2035.000m) Station, Including Associated Cut-Cover And Bored TBM Tunnels"

PREBID QUERIES

S.NO	Date of Query	Page/ Vol No	Clause No	As in Tender Document	Query	Response by CMRL	Addendum
113	1st Set Prebid Queries dated 11th January, 2016	(i)Part], Section -IV (Bidding Forms), CI - 1.1.2 ,Preamble (Retention of Payment for D-Wall Works in Station Boxes), Page : BF-10 (ii) Price Centre D, Page 13F-30 arid Price Centre E, Page BF-31		"in Sir Thiyagaraya station and Kurukkopet station maximum payment will be restricted to 90% of the total value of D-Wall construction. To verify the quality of construction to be as per contractual requirements 10% of the total value of works will be held with the Employer then only this retention money will be released".	Bidder understand that balance 5% payments of Price Centre Ei& Price Center E will be released after completion of remaining miscellaneous works. Hence release of 90% payments upon completion of 0/Wall in station boxes means total retention amount will be (100%- 90 % of 95%) = Itam-ss.s%)= 14.5%. Hence bidder request to delete this retention clause on entirety.	Please refer to Addendum.	Yes
114	1st Set Prebid Queries dated 11th January, 2016	Part1 , Section -IV (Bidding Forms), CI - 1.3.1 , Description of Pricing Centres, Page : BF-13		" the following Key Staff.; Project Manager, QA Manager and Safety Manager, nor employed and on site within 30 days of date of mobilisation in accordance with the Tenderer's Programme, there shall be a deduction of 2 lakhs far each month, or part thereof ,,	Bidder understand that total deduction is 2 lakhs per month due to non deployemnet of requisite Project Manager, QA Manager and Safety Manager as per the tender programme and average decoction per head will be 2/3-0.66 Lakhs due to non deployment. Bidder request to delete this clause.	Not Agreed	No
115	1st Set Prebid Queries dated 11th January, 2016	(i) PartI, Section -IV (Bidding Forms), CI - 1.5 , Payment Concept, Page : BF-14 (ii) Part3, Section -Vill, Partcular Conditions, Part A, Contract Data ,O-14.6, Page: PC-4		(i)" <i>Monthly Statement meeting the minimum value of 1% of Contract Price, and after the Employer's Representative's assessment "</i> (ii) " <i>Minimum amount of interim Payment Certificates 2% of the Accepted Contract Amount"</i>	There is the ambiguity in the minimum amount of Interim Payment Certificates. Bidder understand the the minimum amount of Interim Payment Certificate will be 2% of the Accepted Contract Amount. Bidder request to withdraw minimum amount of Interim Payment Certificate and payment should be on actual work done basis or clarify.	Please refer addendum.	Yes
116	1st Set Prebid Queries dated 11th January, 2016	PartI, Section -IV (Bidding Forms), CI - 1.6.1 (Revision of Price Centers) and CI 1.6.2 (Revision of Schedule of Payments), Page : BF-15.		C1/.6,1 ; "in the unlikely revision of the work" C11.6.2: "The affected price centre Notice of No objection"	Bidder understand that in case of revision of Price Centre and Schedule of Payments, the payment already made for executed items far a particular Priced Centre shall not be reversed. Please confirm.	Not Agreed	No
117	1st Set Prebid Queries dated 11th January, 2016	Part]. , Section -IV (Bidding Forms),Table 1, Schedule F, Page BF-20.		Total Quantity : 2 Nos x 2000 Running Metres, Unit Price in Running Metres.	Bidder understand that for the payment purpose the unit price will be running metres of a single tunnel and not for twin tunnel. Please confirm.	Each single tunnel shall be measured in running meters.	Yes
118	1st Set Prebid Queries dated 11th January, 2016	Para , Section -IV (Bidding Forms),Table 2, Risk Item 14, Page : BF-25.		"Approval from Public Authority and Other Statutory Requirement: The tenderer shall make necessary provisioans in their price to take into account any approval from public authority and statutory requirements".	Bidder understand that necessary cost provision to be kept in their price. Bidder also understand that in case of delay in getting such approval from the authority the bidder shall entitle for both time and cost compensation.	Not Agreed.	No

CONTRACT NO. PHASE-I EXTENSION
UAA-08 "Design Validation and Construction of works of underground station Boxes D-Wall at Sir Thiyagaraya College (CH:1016.000m) & Korrukupet (CH:2035.000m) Station, Including Associated Cut-Cover And Bored TBM Tunnels"

PREBID QUERIES

S.NO	Date of Query	Page/ Vol No	Clause No	As in Tender Document	Query	Response by CMRL	Addendum
119	1st Set Prebid Queries dated 11th January, 2016	PartI, Section -IV (Bidding Forms),Price Centre - F, Page :8F- 34.		"Procurement delivery cost of the OEMetc "	The sum of sub % of the Item no 1 {1.1+1.2+1.3+1.4} is (5%1-46%+40%+8%).99% which is less than 100%. Bidder request to clarify In which items balance 1% will be paid.	Please refer addendum.	Yes
120	1st Set Prebid Queries dated 11th January, 2016	Para, Section -IV (Bidding Forms),Price Centre - F, Page : RF- 34.		"Tunnel from launching shaft near Washermanpet station "	The sum of %of the all items under Price Centre F (Item No 1 to 12) is equal to 101%. Bidder request to clarify. Bidder also understand that there will not be any payment allocation for Item No.8. (Final Pressure Groutings to Linings)	Please refer addendum.	Yes
121	1st Set Prebid Queries dated 11th January, 2016	PartI, Section -IV (Bidding Forms),Price Centre - H, Page : BF- 37.		"Cross Passages in Bored Tunnel ,,, With sump".	Bidder understand that there will not be any payment allocation for Item No 1.1.4 (Permanent Lining) and	Payment allocation is there from the Lumpsum quoted cost.	No
122	1st Set Prebid Queries dated 11th January, 2016				1.20 (Sump Construction). Please clarify.	Payment allocation is there from the Lumpsum quoted cost.	No
123	1st Set Prebid Queries dated 11th January, 2016	(i)Part3, Section - VIII, PC (Part A- Contract Data), Cl. 4.2 - Performance Security, Page PC-3 (ii) Part3, Section -VIII, SP-6 (Part B- Particular Conditions), Cl. 4.2 - Performance Security, Page;2-3		(i)"The Performance Security will be in the form of a "demand guarantee" or "performance bond" in the amount(s) of 7.516percent of the Accepted Contract Amount (ii)".....The Performance Security shall be issued by public sector undertaking bank (P50) selected by the Employer,	Presuming higher contract value bidder request to reduce the Performance Security % from 7.5% to 5%. Please accept Bidder also request to provide the name of the public sector undertaking bank (P50) selected by the Employer.	Not Agreed	No
124	1st Set Prebid Queries dated 11th January, 2016	Part3, Section -VII, General Conditions (GC), Cl. 4.13 - Right of Way and Facilities, Page GC-23		"The Contractor shall obtain, at his risk and cost, any additional rights of way or facilities outside the Site which he may require for the purposes of the Works"	From the past experience bidder understand that entire Rights of Way is to be arrange and delivered by the Employer to the Contractor. In case of delay in delivery of right of way the bidder is entitle for compensation both in terms of time and cost. Please clarify.	Not Agreed	No
125	1st Set Prebid Queries dated 11th January, 2016	Part3, Section -VII, General Conditions (GC), Cl. 17.6 - Limitation of Liability, Page GC-70 and Particular Condition (PC), Part A -Contract Data, Page :1-4		"Neither Party shall be liable to the other Party for loss of use of any Works, loss of profit, loss of any contract or for any indirect or consequential loss or damage which may be suffered by the other Party in connection with the Contract, other than as specifically provided in Sub-Clause 8.7 [Delay Damages]; Sub-Clause 11.2 (Cost of Remedying Defects); sub-Clause 15.4 [Payment after Termination]; Sub-Clause 16.4 [Payment on Termination]; Sub-Clause 17.1 [Indemnities]; Sub-Clause 17.4 (b) (Consequences of Employer's Risks) and Sub-Clause 17.5 [intellectual and industrial Property Rights]"	Bidder request to delete Sub-Clause 8.7 (Delay Damages), Sub-Clause 11.2 [Cost of Remedying Defects] ,Sub-Clause 17.4 (b) [Consequences of Employer's Risks] from this clause as per the standard practice of the contract. Please confirm the deletion of the said clause.	Not Agreed	No
126	1st Set Prebid Queries dated 11th January, 2016	Part3, Section -VIII, Particular Condition (PC), Part A - Contract Data,CP 18.2 (d) Page : 1-S		"Maximum amount of deductables for insurance of the Employer Risk 1% of the contract amount of each occurrence"	Bidder understand that the maximum amount of deductables (1% of the contract amount) shall be based on General Insurance Guide Line. Please clarify.	No change in contract condition	No

CONTRACT NO. PHASE-I EXTENSION

UAA-08 "Design Validation and Construction of works of underground station Boxes D-Wall at Sir Thiyagaraya College (CH:1016.000m) & Korrukupet (CH:2035.000m) Station, Including Associated Cut-Cover And Bored TBM Tunnels"

PREBID QUERIES

S.NO	Date of Query	Page/ Vol No	Clause No	As in Tender Document	Query	Response by CMRL	Addendum
127	1st Set Prebid Queries dated 11th January, 2016	Part3, Section -VIII, Specific Provisions (SP), Part B - Paricular Conditions, SP-4, Sub Cl-2.5 Employer's Claim. Page : 2-3.		'Some of the circumstancess (vii) Any other unforeseen circumstances"	Bidder request to specify the probable unforeseen circumstancess or delete pars "(vii) any other unforeseen circumstances".	No change in contract condition	No
128	1st Set Prebid Queries dated 11th January, 2016	Part3, Section -VIII, Specific Provisions (SP), Part B - Paricular Conditions, SP-17, Sub Cl-8.5 Delay Caused by Authorities. Page : 2-8.		"Without prejudice__ ifi (iv)._ (vi) From delay in obtaining any permissions, consents or approvals of whatsoever nature required by any Law to commence or carry out construction, or open the Works for public use, or	The Contractor can put their best efforts to get the necessary permissions, consent or approval from the aothority on time but any delay caused by the authority due to some other reason the contractor would not be responsible for the same. Hence the bidder request to remeove the para (vi) from this clause and allow extension of time due to delay caused by the authority in obtaining permission, consents or approval in whatsoever nature required by any law to commence and carryout of the construction.	Not Agreed	No
129	1st Set Prebid Queries dated 11th January, 2016	Part3, Section -VIII, Specific Provisions (SP), Part 8 - Paricular Conditions, SP-20, Sub Cl-13.1, Right to Vary. Page ; 2-10.		"Add the following '0)The lumpsum items included in the Pricing Documents will not be eligible for revisison"	Bidder request to keep the provision for revision of rate for the lumpsum items in case of changes on the Employer's Requirement from the tender documents which could have substatial cost impact to the Contractor. Please confirm.	Not Agreed	No
130	1st Set Prebid Queries dated 11th January, 2016	Part3, Section -VIII, Specific Provisions (SP), Part B - Paricular Conditions, SP-23, Sub Cl-14.1, The Contract Price. Page : 2- 14.		"Contract price means the price excluding TNVAT, Customs duties and other taxes. Price Variation will be calculated only on Contract Price as defined above"	Bidder request to specify the other taxes in the definition of Contract price as the Price Variation calculation will be based on the Contract Price.	Refer to Addendum, contract condition prevails	Yes
131	1st Set Prebid Queries dated 11th January, 2016	Part3, Section -VIII, Specific Provisions (5P), Part B - Paricular Conditions, SP-26, Sub 0-2.1, Right of Access to the Site, Page : 2-17.		In case of delay in handing over of the site by the Employer, the Contractor will be given extension of time only. The payment in the extended period in such cases will be with price adjustment effective from the original date of completion.	Bidder request to add cost compensation due to delay in handing over of the site by the Employer. Due to such delay there may be idling of deployed resources of the Contractor which in turn will be the additional cost impact to the Contractor, Please accept.	Not Agreed	No
132	1st Set Prebid Queries dated 11th January, 2016	Part2, Employers Requirements- Construction, Casting Yard and Batching Plant, Page -D3		"Availability of Land will be Intimated Later"	Bidder understands that the land for casting yard will be available from the day one of the Contract. In case of delay in getting such land the Contrator will be compensated both in terms of time and cost. Please confirm.	Contractor needs to identify the land and factor the price in his bid. Incase CMRL provides the land at a later date it will be on monthly payment basis, and the contractor is free to accept or reject the offer.	No
133	1st Set Prebid Queries dated 11th January, 2016	Part2, Employers Requirements- Construction, Muck Disposal Site, Page - 113		"Suitable landfor disposal of muck shall be indentified within a raiodius of 32 Km from the Washermanpet TBM Launching Shaft"	Bidder understand that the distance of muck disposal area shall be within a raiodius of 32 Km from Washermanpet Launching Shaft. In case the distance of such muck disposal area will be more than 32 km then additional cost of the disposal of muck shall be compensated to the Contractor. Please confirm.	Refer to addendum	Yes

CONTRACT NO. PHASE-I EXTENSION
UAA-08 "Design Validation and Construction of works of underground station Boxes D-Wall at Sir Thiyagaraya College (CH:1016.000m) & Korrukupet (CH:2035.000m) Station, Including Associated Cut-Cover And Bored TBM Tunnels"

PREBID QUERIES

S.NO	Date of Query	Page/ Vol No	Clause No	As in Tender Document	Query	Response by CMRL	Addendum
134	1st Set Prebid Queries dated 11th January, 2016	Part2, Employers Requirements- Appendix 2B, Construction, Contrac Key date and Completion date, Page -2B-1 and Tabel of Liquidated Damages, Section - VIII, Particular Conditions (PC-5), Page: 1-5 and		"Liquidated Damages in respect of two or more Key Dates relating to a single station or tunnel may run concurrently, and the Contractor will be liable for the aggregate of Liquidated Damages for all delayed Key Date"	Bidder understand that the liquidated damages imposed on the intermediate key dates shall be refunded to the Contractor on achievement of subsequent key dates and finally on achievement of final completion Key date all liquidated damages imposed on all the intermediate key dates shall be refunded to the Contractor. Please confirm.	original contract condition prevails	No
135	1st Set Prebid Queries dated 11th January, 2016	Part2, Employers Requirements- Functional, Scope of works (Vi), Page -62		Auxiliary utilities systems for tunnels and cross passages including ventilation, tunnel lighting, and connections to station D-wall	The scope of works is not clear. Bidder understands that the scope of work comprises of only the d/walls for the stations & the launching/retrieval shafts, 2 tunnel drives by TBM, cross passages, & 1st stage trackbed concrete. Tunnel ventilation and lighting cannot be in the scope of works. Also, the d/walls or superstructure walls for the entry/exit & ventilation shafts are excluded. Neither is any excavation for stations included. Kindly confirm. Please also state whether the struts/walers which will be fixed in the launching / retrieval shafts will have to be considered as supplied to CMRL, since the same cannot be taken out. Further, bidder understands that only structural design, limited to validation of the Employer's design is in the scope & MEP & architectural designs are excluded. Also, no interface with system-wide (interfacing) contractors are needed. Hence the requirements stated in the specifications are ignored. Bidder assumes that all loads considered by CMRL for structural designs are sacrosanct & bidders design of d/walls will depend on the same	Please refer to Scope of work, contract conditions Prevails	No
136	1st Set Prebid Queries dated 11th January, 2016	Part2, Employers Requirements- Appendix 28, Contrac Key date and Completion date, Page -26-1		KD2 - "Completion of launching shaft, erecton and commissioning of TBM"- 180 clays	Based on the scope of the work, bidder request to extend the key date to 270 days. Please accept.	Refer to Addendum.	yes
137	1st Set Prebid Queries dated 11th January, 2016	Part2, Employers Requirements- Appendix 26, Contrac Key date and Completion date, Page -28.-1		KD3 - "Construction of Sir Thiyagaraya College Station main box Dwall" - 300 days	Based on the scope of the work, bidder request to extend the key date to 390 days. Please accept.	Refer to Addendum.	yes
138	1st Set Prebid Queries dated 11th January, 2016	Part2, Employers Requirements- Appendix 26, Contrac Key date and Completion date, Page -26-1		KD4 - "Construction of TBM tunnel upto Sir Thiagaraya College Station"- 360 days	Based on the scope of the work, bidder request to extend the key date to 450 days. Please accept.	Refer to Addendum.	yes

CONTRACT NO. PHASE-I EXTENSION
UAA-08 "Design Validation and Construction of works of underground station Boxes D-Wall at Sir Thiyagaraya College (CH:1016.000m) & Korrukupet (CH:2035.000m) Station, Including Associated Cut-Cover And Bored TBM Tunnels"

PREBID QUERIES

S.NO	Date of Query	Page/ Vol No	Clause No	As in Tender Document	Query	Response by CMRL	Addendum
139	1st Set Prebid Queries dated 11th January, 2016	Part2, Employers Requirements- Appendix 28, Contrac Key date and Completion date,Page -2B-1		KDS - "Construction of Korrukupet Station main box Dwar - 450 days	Based on the scope of the work, bidder request to extend the key date to 510 days. Please accepct.	Refer to Addendum.	yes
140	1st Set Prebid Queries dated 11th January, 2016	Part2, Employers Requirements- Appendix 26, Contrac Key date and Completion date,Page -26-1		KD6 - "Construction of TBM tunnel upto Korrukupet Station" -540 days	Based on the scope of the work, bidder request to extend the key date to 600 days. Please accepct.	Refer to Addendum.	yes
141	1st Set Prebid Queries dated 11th January, 2016	Part2, Employers Requirements- Appendix 2B, Contrac Key date and Completion date,Page -2B-1		KD7- "Construction of cross passages without sump in oil respect"-630 days	Based on the scope of the work, bidder request to extend the key date to 720 days. Please accepct.	Refer to Addendum.	yes
142	1st Set Prebid Queries dated 11th January, 2016	Part2, Employers Requirements- Appendix 2B, Contrac Key date and Completion date,Page -2B-l		108 - "Construction of cross passages with sump in all respect" - 660 days	Based on the scope of the work, bidder request to extend the key date to 750 days. Please accepct.	Refer to Addendum.	yes
143	1st Set Prebid Queries dated 11th January, 2016	Part2, Employers Requirements- Appendix 2B, Contrac Key date and Completion date,Page -2B-1		KD9 - "Laying of first stage concrete in IBM tunnel"- 720 days	Based on the scope of <i>the</i> work, bidder request to extend the key date to 840 days.Please accepct.	Refer to Addendum.	yes
144	1st Set Prebid Queries dated 11th January, 2016	General		All Drawings.	Bidder request to kindly provide the CAD file of the alignment and station structures etc. Please accepct.	Not Agreed	No
145	1st Set Prebid Queries dated 11th January, 2016	General			Bidder understand that client will provide necessary approval from Indian Railway for crossing under the existing railway track just after the launching shaft at Washermanpet. Please confirm.	Approvals to be taken by the contractor, CMRL will provide necessary assistance.	Yes
146	1st Set Prebid Queries dated 11th January, 2016	General		-	Bidder understand that 5000 sqm of temporary land adjacent to launching shaft at Washermanpet for site set up for TBM tunneling work and for access of TBM and logistics is available. Please confirm.	Please see Work area Drawing for Washermenpet launching Shaft. This is the only area available.	Yes
147	1st Set Prebid Queries dated 11th January, 2016	NIT of Corrigendum 2, Item No. 10: Date & Time of Submission of Tender		04.02.2016 (up to 14:00 hrs) at office of the Chief General Manager (UG-Construction)....	Considering the complexity of the proposed work, Bidder earnestly request for extension of bidsubmission date by further 30 days. Please accept.	Date extended upto 11-02-2016. Please refer addendum.	Yes
148	1st Set Prebid Queries dated 11th January, 2016	General			Bidder request to provide the as built layout plan of Washermanpet station near the launching shaft of UAA-08.	Relevant information is already available on drawings.	No

CONTRACT NO. PHASE-I EXTENSION
UAA-08 "Design Validation and Construction of works of underground station Boxes D-Wall at Sir Thiyagaraya College (CH:1016.000m) & Korrukupet (CH:2035.000m) Station, Including Associated Cut-Cover And Bored TBM Tunnels"

PREBID QUERIES

S.NO	Date of Query	Page/ Vol No	Clause No	As in Tender Document	Query	Response by CMRL	Addendum
149	1st Set Prebid Queries dated 11th January, 2016	General			Bidder understand that the permission for demolition of the existing building at Sir Thiyagaraya College Station towards Washermanpet, retrieval shaft area and Korrukupet Sation shall be available from principal employer at very beginning of the project. Please confirm.	Refer to addendum, land will handed over progressively	Yes
150	1st Set Prebid Queries dated 11th January, 2016	General		-	Bidder understand that the blockage of entire road area of T H Road of Korrukupet Station box is under the scope of principal employer. Please confirm.	This is in the scope of contractor, CMRL will provide necessary assistance	No
151	1st Set Prebid Queries dated 11th January, 2016	General		-	Bidder understand that all the permissions for permanent and temporary utility diversion from <i>concern</i> local authorities are under the scope of principal employer. Please confirm.	This is in the scope of contractor, CMRL will provide necessary assistance	No
152	1st Set Prebid Queries dated 11th January, 2016	Drawing No. DDC101-PD-TUN-ST-DW-13121		-	As per the attached segment drawings it is understood that straight bolt will be used for segments, can we go for curved bolt instead of straight bolt. Please confirm.	Not Agreed.	No
153	1st Set Prebid Queries dated 11th January, 2016	Drawing No. DDC101-PD-TUN-CW-DW-13101			As per the attached segment drawings it is understood that precast slab will be used as permanent walkway, can we go for galvanised steel structure instead of precast slab. Please confirm.	This work is not in the scope of this contract.	No
154	1st Set Prebid Queries dated 11th January, 2016				Can bidder propose alternative design for the segmental lining? Please confirm.	No. Design is in the scope of DDC.	No
155	1st Set Prebid Queries dated 11th January, 2016				Can bidder optimize the segmental lining design based on the additional Soil Investigation results? Please confirm.	No. Design is in the scope of DDC.	No
156	1st Set Prebid Queries dated 11th January, 2016				Bidder request to kindly provide the lab lest results for the tender boreholes. Please confirm.	Lab test results provided refer to addendum.	Yes
157	1st Set Prebid Queries dated 11th January, 2016				Can bidder optimize the ground improvement, permanent lining and temporary lining details of the CPs based on the additional Soil Investigation results?	Temporary ground improvement is part of the contractor's design.	No
158	1st Set Prebid Queries dated 11th January, 2016				Can bidder propose alternative design for the temporary works such as temporary bracing for CP Construction?	Design of Tempopary works/ Bracing/Support for CP's is a part of contractor scope.	No
159	1st Set Prebid Queries dated 11th January, 2016				In some drawings mentioned as "Detailed Design to Follow" - dose it mean Employer will provide or bidder has to design it in detail?	Employer to provide. Design is in scope of DDC.	No
160	1st Set Prebid Queries dated 11th January, 2016				As per the tender document the actual scope of work is "Design validation and construction of underground station boxes Dwell at Sir Thiyagaraya College and Korrukupet station, including associated cut & cover and bored TBM tunnels", but as per our site visit bidder came to know that associated cut & cover work is not under the scope of this package, kindly confirm the exact scope of work.	Cut and cover mentioned here refers to the cut and cover tunnel in the launching shaft area.	No

CONTRACT NO. PHASE-I EXTENSION
UAA-08 "Design Validation and Construction of works of underground station Boxes D-Wall at Sir Thiyagaraya College (CH:1016.000m) & Korrukupet (CH:2035.000m) Station, Including Associated Cut-Cover And Bored TBM Tunnels"

PREBID QUERIES

S.NO	Date of Query	Page/ Vol No	Clause No	As in Tender Document	Query	Response by CMRL	Addendum
161	2nd Set Prebid Queries dated 20th January, 2016	2nd Set Prebid Queries dated 20th January, 2016		subdouse 3: "The contractor shall engage the lead detailed designer who shall validate prepare the design of the permanent works and temporary works & the contractor shall establish an office his lead design team near the site area Chennai Subcfause 4: 'The Contractor shall ensure that the Designer continues to be represented in Chennai at all times by staff whose seniority and experience ore to the satisfaction of the Employer's Representative and whose representative is available on the Site as necessary or as required by the Employer's Representative."	Bidder understand that the entire permanent work design is under ODC/CMRL Scope. But as per the stated clause the contractor must have his own designer for design validation during post tender stage for entire tenure of the project. Bidder request to clarify this contradiction whether the contractor has to kept thier own designer for permanent works during post tender stage. Since the permanent work is not under bidder scope , bidder request to clarify the sanctity of the submission of the Design Certificate at per Attachment Cl. Hence bidder request to delete this "Certificate" from the bid document.	Refer to Addendum	Yes
162	2nd Set Prebid Queries dated 20th January, 2016	Part2, Employer's Requirement, Design, Volume-1, Section C, Para C1, Introduction, Subclause 3 & 4 ,Page Cl and Attachment C1 (Design Certificate) Page C-9		"This is to certify that we have validated the design and drawings from constructability point of view as per employer's requirement, technical specifications, construction specifications as stated in this contract. We also confirm that the design is fit for purpose"	Bidder understand that the entire permanent work design is under DDC/CMRL Scope. How bidder can confirm that the design is fit for the purpose. Bidder request to clarify or delete this "Form" from Bid document.	Refer to Addendum	Yes
163	2nd Set Prebid Queries dated 20th January, 2016	Paull, Section -IV (Bidding Forms),Design Validation Form the Tendered, Page : 8F-713		"The tenderer shall submit the following documents duly completed as part of envelope-3 (Technical Proposal) in accordance with DB 17 List of Manuals required for operation and maintenance..... Design for Temporary works "	As per standard practice the list of manuals required for operation and maintainance shat be supplied by the DDC/Employer. Please clarify whether bidder has to submit the same or DDC /Empoyer will supply.	Refer to Addendum	Yes
164	2nd Set Prebid Queries dated 20th January, 2016	Part1 , Bidding Procedures, Cl 45.1.2, Supplimentary Instructions to Bidder, Page : SIB-4		"The tenderer shall submit the following documents duly completed as part of envelope-3 (Technical Proposal) in accordance with DB 17 List of Manuals required for operation and maintenance..... Design for Temporary works "	Bidder understand that the entire permanent work design is under DDC/CMRL Scope. How bidder can confirm that the design is fit for the purpose. Bidder request to clarify or delete this "Form" from Bid document.	Refer to Addendum	Yes
165	2nd Set Prebid Queries dated 20th January, 2016	Part2, Employers Requirements- Construction, Casting Yard and Batching Plant, Page -D3		"Availability of Land will be Intimated Later"	Though it has been clarified In the MOM of prebid meeting dated 12.01.16 that bidder has to arrange the land for Casting yard. However bidder once again request for arrangement of land for Casting Yard by CMRL.	Refer to Addendum	Yes
166	2nd Set Prebid Queries dated 20th January, 2016	MOM Prebid Meeting Dated 12.01.16		General	Since the addendum not issued as on date bidder request to allow for submission of further query if any after getting the addendum.	Not agreed	No
167	2nd Set Prebid Queries dated 20th January, 2016	Partl , Section -IV (Bidding Forms), Schedule of Adjustment Data , Page : BF-08		Price Variation Clause Component: a) Fixed : 0.3, b) Labour 0.1 -0.3 , c) Cement 0.05 - 0.25, d) Steel 0.05 - 0.15, e) Fuel 0.15-0.35	Bidder request to reduce the Fixed component from 30% to 15% and modify other component accordingly.	Refer to Addendum	Yes

CONTRACT NO. PHASE-I EXTENSION
UAA-08 "Design Validation and Construction of works of underground station Boxes D-Wall at Sir Thiyagaraya College (CH:1016.000m) & Korrukupet (CH:2035.000m) Station, Including Associated Cut-Cover And Bored TBM Tunnels"

PREBID QUERIES

S.NO	Date of Query	Page/ Vol No	Clause No	As in Tender Document	Query	Response by CMRL	Addendum
168	2nd Set Prebid Queries dated 20th January, 2016	General		Design Validation"	Bidder request to clarify in detail the scope of "Design Validation" during pre tender and post tender stages.	Refer to Addendum. For Validation Certificate	Yes
169	2nd Set Prebid Queries dated 20th January, 2016	Part-2 Section VI Volume-1, Employer's requirement, Section B, Employer's requirement - Functional, Page no. 8-2 Clause No. B2 - Scope of work		"82 SCOPE OF WORKS (1)The Permanent and Temporary works shall comprise (i)Survey and Investigation including Soil Investigation, Topographic Survey, Existing Building Survey, Utilities Investigation, Existing Water Wells Investigation as necessary.. (viii) Protection and relocation of utilities; "	In the bid documents it is mentioned that the protection & relocation of utilities is within the scope of work of Contractor. But no utility drawings has been provided for Station locations, Launching & Retrieval shaft locations in the bid document. Since there is no BOQ items in the price centre how this items will be paid. Please clarify.	Refer to Addendum	Yes
170	2nd Set Prebid Queries dated 20th January, 2016	Part-2 Section VI Volume-1, Employer's requirement, Appendix 213, Page no. 26-1, Contract Key Dates.		"KD-02 - Completion of Launching shaft, Erection and Commissioning of TBM..... KD-06 - Construction of TBM Tunnel upto Korrukupet Station....."	The Key Date KD-02 as provided is applicable only for commissioning of 1st TBM or for both TBMs. Please clarify. The Key Date KD-06 as provided is applicable only for Breakthrough of 1st TBM or for both TBMs. Please clarify.	KD02: Commissioning of Both TBMs , KD06 Both TBM's as well	No
171	2nd Set Prebid Queries dated 20th January, 2016	Part-2 Section VI Volume-1, Employer's requirement, Section B, Employer's requirement - Functional, Page no. B-1 Clause No. B2 - Scope of work.		B2 SCOPE OF WORKS (i)The Permanent and Temporary works shall comprise..... (ii) The demolition of existing buildings, which may or may not be as shown on the drawings, the exact numbers and locations to be confirmed by the Contractor; and	In the Key Dates for which LD is applicable, has the time for demolition of buildings at the two station locations been considered. Please clarify. Timeline for clearance of occupancy of the buildings to be demolished, is not mentioned in the bid document. It is assumed that the buildings shall be available for demolition from day one of the Contract. Please clarify.	Contract condition prevails for LD related issues. Demolition of Existing Structure in the work area boundary is the responsibility of the constructor. The land will be handed over to the constructor progressively in stages, refer to addendum.	No
172	2nd Set Prebid Queries dated 20th January, 2016	Part1 , Section -IV (Bidding Forms),Form of Bid Security (Bank Guarantee), Page : BF-71		We have been Under Loan Agreement No (Insert Loan Agreement Number)	Bidder request to provide the Loan agreement number required for filling of Form of Bid Security.	Refer to Addendum	Yes
173	1st Set Prebid Queries dated 5th January, 2016	ITB-4, Cl. 2		Source of Funds	Kindly provide source and availability of Funds for the Project.	Refer to Addendum	Yes
174	1st Set Prebid Queries dated 5th January, 2016	IFB-1, Cl. 4 & 4(i)		A complete set of the Bidding Document may be purchased....to be submitted along with the bid.	Bidders, who have purchased the documents in hard copies by paying Rs. 25000/- are not required to pay fee of Rs. 20000/- as per Cl. 4(i). Please clarify.	Clause are self explanatory	No
175	1st Set Prebid Queries dated 5th January, 2016	ITB-8 & 9, Cl. 7.1 & 7.5		Clarification of Bidding Documents	Clause 7.1 and 7.5 are contradicting each other. We request time till 14 days prior submission of bid for submission of pre-bid queries.	The pre-bid queries submission date has already been extended 20/01/2016	No

CONTRACT NO. PHASE-I EXTENSION
UAA-08 "Design Validation and Construction of works of underground station Boxes D-Wall at Sir Thiyagaraya College (CH:1016.000m) & Korrukupet (CH:2035.000m) Station, Including Associated Cut-Cover And Bored TBM Tunnels"

PREBID QUERIES

S.NO	Date of Query	Page/ Vol No	Clause No	As in Tender Document	Query	Response by CMRL	Addendum
176	1st Set Prebid Queries dated 5th January, 2016	ITB-12 & 13, Cl. 14.1		Documents establishing the Eligibility of Plant, Materials and Services	Since tender is only for civil works, do bidders need to provide Country of Origin Declarations. If Yes, kindly provide - 1. Format of the declaration (not provided in section-IV) 2. For which materials such declaration is to be provided	Refer to Addendum	Yes
177	1st Set Prebid Queries dated 5th January, 2016	ITB-14, Cl. 16(b)		a list giving full particulars, including available sources, of all spare parts, special tools, etc., necessary for the proper and continuing functioning of the Plant for the period specified in the BDS, following completion of the Works in accordance with the provisions of Contract; and	The tender documents are only for civil works and this does not include supply of any Plant, therefore this required needs to be deleted. Else, kindly elaborate.	Not agreed	No
178	1st Set Prebid Queries dated 5th January, 2016	-		General	All the Declarations/ Undertakings asked in the tender submission can be provided by the Bidder on its letterhead. Kindly confirm.	Agreed	No
179	1st Set Prebid Queries dated 5th January, 2016	SIB-3, 10th Line from Top		complexity in the last in Clause 1.1.3(b) & (c)	Ref. no. of Clause given seems to be wrong. Kindly provide the correct ref. nos.	Refer to Addendum	Yes
180	1st Set Prebid Queries dated 5th January, 2016	SIB-3, 2nd and 4th Line from Bottom		referenc to various clause nos.	Ref. no. of Clause/s given seems to be wrong. Kindly provide the correct ref. nos.	Refer to Addendum	Yes
181	1st Set Prebid Queries dated 5th January, 2016	SIB-4, Cl. 45.1.2.1(a)		The tenderer shall submit the following. - List of Manuals required for operation and maintenance	This being only civil works, no such requirements are envisaged. Kindly confirm and delete the requirement.	Not agreed	No
182	1st Set Prebid Queries dated 5th January, 2016	SIB-4, Cl. 45.1.2.1(a)		The tenderer shall submit the following - Details of insurance providers	We presume Bidders need to provide tentative list of insurance companies from whom Bidders may procure the insurance policies, if work is awarded to them. Kindly confirm. If not, kindly elaborate.	Please provide the prospective list of insurance providers	No
183	1st Set Prebid Queries dated 5th January, 2016	SIB-4, Cl. 45.1.2.1(a)		The tenderer shall submit the following - Schedule of Guarantee - Spare Parts	Since there is no Plant Supply in the scope of this tender, requirement of Schedule of Guarantee and Spare Parts is not relevant to this tender. Kindly confirm.	Not required.	No
184	1st Set Prebid Queries dated 5th January, 2016	BDS-4, ITB 37.1		The source of exchange rate shall be : Reserve Bank of India (RBI)	Since exchange rate for all the currencies is not available on RBI website, we request use of exchange rates available at www.xe.com or www.oanda.com . Kindly permit.	Not agreed	No
185	1st Set Prebid Queries dated 5th January, 2016	EQC-2, Cl. 1.1.3(a)		Subcontracting	Please confirm whether Bidder need to submit an undertaking for fulfilling this requirement on its letterhead.	Not agreed	No
186	1st Set Prebid Queries dated 5th January, 2016	EQC-3, Cl. 2(i)(a)		For turnover or financial data required for each year - Exchange rate prevailing on the last day of the respective calendar year.	Most of the Indian companies maintain its books of account on April to March FY basis. In such a case, exchange rate applicable on last day of the FY may be used. Please confirm.	Not agreed	No
187	1st Set Prebid Queries dated 5th January, 2016	EQC-10, Cl. 2.3.3(ii)		The Bidder shall also demonstrate, to the satisfaction of the Employer, that it has adequate sources of finance to meet the cash flow requirements on works currently in progress and for future contract commitments.	Kindly confirm if information provided in the Form FIR-2 is certified by Auditor shall be sufficient for complying to this requirement.	Agreed	No
188	1st Set Prebid Queries dated 5th January, 2016	BF-4, Cl. (d)		We offer to design and build, in conformity with the Bidding Documents....	We understand that this contract shall be an item rate (quantities remeasurable) basis and design will be in Employer's scope. Kindly confirm and amend the form.	Refer to Addendum. Quantities are not re-measurable as they are as per the Design Drawings	Yes

CONTRACT NO. PHASE-I EXTENSION
UAA-08 "Design Validation and Construction of works of underground station Boxes D-Wall at Sir Thiyagaraya College (CH:1016.000m) & Korrukupet (CH:2035.000m) Station, Including Associated Cut-Cover And Bored TBM Tunnels"

PREBID QUERIES

S.NO	Date of Query	Page/ Vol No	Clause No	As in Tender Document	Query	Response by CMRL	Addendum
189	1st Set Prebid Queries dated 5th January, 2016	BF-10, Cl. 1.1 (second last Para)		The total amount of each of the Price Centers B to I shall be equal to 95% of the Sum of the Price Centers inserted into the Pricing Summary in Clause 1.7.	Percentage mentioned as 95% seems to be wrong. Kindly confirm.	Refer to Addendum	Yes
190	1st Set Prebid Queries dated 5th January, 2016	BF-17, Note (1)		Price Centre A has not been priced but will be 7.5% of the price centre totals of Price centres B to I quoted in the table.	We presume that Bidder shall quote his 100% cost in the table given at Cl. 1.7 (BF-16) in each Price Center from B to I. Kindly confirm.	Refer to Addendum	Yes
191	1st Set Prebid Queries dated 5th January, 2016	BF-16, 1.7 (Pricing Summary) and 13F-18 (Schedule-B)		-	Please confirm that the amounts to be quoted in the table at Cl. 1.7 (Pricing Summary) and in the Table-1 at BF-18 to BF-23 shall be the same against a particular Price Center NOT 92.5%.	Refer to Addendum	Yes
192	1st Set Prebid Queries dated 5th January, 2016	BF-29, Note below the Table		Price Center "A" Preliminaries shall equal 7.5% of the Price Center Totals for Price Centers B to I, excluding TN VAT	We have elaborated the clause as under for clarity: Amount quoted under Price Center fo Payments - Price Centre - A (Preliminaries) shall be equal to 7.5% of the Price Centre Totals for Price Centers B to I quoted in Table given at Cl. 1.7 (BF-16) , excluding only TN VAT. Please confirm if our understanding is correct.	Refer to Addendum	Yes
193	1st Set Prebid Queries dated 5th January, 2016	BF-33		Heading of the Table is given as "Price Centre - D"	There seems to be a typographical error. It should be - "Price Centre - E". Please confirm.	Refer to Addendum	Yes
194	1st Set Prebid Queries dated 5th January, 2016	BF-34, Item No. 1.1 to 1.4		-	The total of percentages given aagainst the sub-item nos. 1..1 to 1.4 should be 100. Kindly clarify.	Refer to Addendum	Yes
195	1st Set Prebid Queries dated 5th January, 2016	BF 34 & BF 35		-	The total of percentages given aagainst the all the items should be 100. Kindly clarify.	Refer to Addendum	Yes
196	1st Set Prebid Queries dated 5th January, 2016	BF-27 to BF-45		-	Please clarify whether Bidder needs to insert Rate and Amount Column against all the table for each Price Centre and fill in the data and submit.	Refer to Addendum	Yes
197	1st Set Prebid Queries dated 5th January, 2016	BF-46, first bullet point		Scope Analysis- Comprehensive study of balance works including evaluation of scope of balance work and the appropriate methodology to finish the same within stipulated time.	Kindly provide details of Balance Works.	Refer to Addendum	Yes
198	1st Set Prebid Queries dated 5th January, 2016	BF-46		- List of Manuals required for operation and maintenance - Details of insurance providers - Schedule of Guarantee - Spare Parts	This being only civil works, no such requirements are envisaged. Kindly confirm and delete the requirement.	Not agreed	No
199	1st Set Prebid Queries dated 5th January, 2016	BF-47 (Form SOG: Schedule of Guarantee)		-	This being only civil works, no such requirements are envisaged. Kindly confirm and delete the requirement.	Not agreed	No
200	1st Set Prebid Queries dated 5th January, 2016	BF-54 (Form SPA: Spare Parts)		-	This being only civil works, no such requirements are envisaged. Kindly confirm and delete the requirement.	Not agreed	No
201	1st Set Prebid Queries dated 5th January, 2016	BF-58 to BF-69 (Forms)	USD Equivalent....	We presume all the data is required to be produced in INR Equivalent as all the Evaluation and Qualification Criteria requirements are in INR. Kindly confirm.	Agreed	No

CONTRACT NO. PHASE-I EXTENSION
UAA-08 "Design Validation and Construction of works of underground station Boxes D-Wall at Sir Thiyagaraya College (CH:1016.000m) & Korrukupet (CH:2035.000m) Station, Including Associated Cut-Cover And Bored TBM Tunnels"

PREBID QUERIES

S.NO	Date of Query	Page/ Vol No	Clause No	As in Tender Document	Query	Response by CMRL	Addendum
202	1st Set Prebid Queries dated 5th January, 2016	BF-71 (Form of Bid Security (Bank Guarantee))		We have been informed that under Loan Agreement No. [insert Loan Agreement Number].	Kindly provide the Loan Agreement Number, else modify the format.	Refer to Addendum	
203	1st Set Prebid Queries dated 5th January, 2016	BF-71 (Form of Bid Security (Bank Guarantee))			As per the GoI guidelines, usage of Structured Financial Messaging System (SFMS) for sending and receiving Inland Letters of Credit and Inland Bank Guarantees has been made mandatory for the Banks. Therefore, request you to provide following Banker details of CMRL: 1. Beneficiary Name: 2. Beneficiary Bank Name: 3. Bank Branch Address: 4. Account No.: 5. IFSC Code of teh Branch:	1. Beneficiary Name: Chennai Metro rail Limited. 2. Beneficiary Bank Name: Corporation Bank 3. Bank Branch Address: Ashok Nagar, Chennai - 600083 4. Account No: CBCA01000531 5. IFSC Code of teh Branch: CORP0000578	No
204	1st Set Prebid Queries dated 5th January, 2016	BF-71 (Form of Bid Security (Bank Guarantee))			Following clause shall be added by the Bank at the end of the Bank Guarantee towards Bid Security: Notwithstanding anything contained herein: (a) Our liability under this Bank Guarantee shall not exceed Rs. (b) This Bank Guarantee shall be valid up to (c) We are liable to pay the guarantee amount or part thereof under this Bank Guarantee only & only if you serve upon us a written claim or demand on or before	Refer addendum	Yes
205	1st Set Prebid Queries dated 5th January, 2016	GC-52, Section 141- General Conditions (Cl. 13.5) & Page 1-4 of Section VIII: Particular Conditions (PC-4) - Provisional Sums (Cl. 13.5.(b)(ii))		Provisional Sums 15%	We presume there are no provisional sum items given in the Price Centers. Kindly clarify.	Refer addendum	Yes
206	1st Set Prebid Queries dated 5th January, 2016	BF-9, Cl. 1.1 (seventh pars)		The rates to be quoted..., DSR 2015 will be adopted.	We presume this clause is not relevant for this tender. Kindly confirm.	Not accepted	No
207	1st Set Prebid Queries dated 5th January, 2016	BF-10, Cl, 1.1.1		...The rates should be based on TN PWD schedules rates 2015. For the items not available in TNPWD schedule, DSR 2015 will be adopted. No escalation will be allowed....	Kindly clarify what relevance TNPWD rates are having with this tender. (Also please note that this is not an % above/ below type of tender wherein Bidder quotes +/-% on given rates, therefore SOR of TNPWD or CPWD shall not be applicable.)	Not agreed. Refer to Addendum	Yes
208	1st Set Prebid Queries dated 5th January, 2016	BF-11, Cl. 1.1.3		Post completion maintenance of Bored tunnel works	Please confirm how Contractor's overheads and profit margin will be paid for such obligations. Also provide the time period for which such obligations will be fulfilled by the Contractor.	Not agreed	No
209	1st Set Prebid Queries dated 5th January, 2016	BF-11, Cl. 1.3, Last para		Price Center '1 represents a Schedule of Rates for chartered utilities, and miscellaneous items such as road dismantling and demolishing etc and the same shall be paid as per the latest schedule of rates (SOR), Southern Railways CPWD (SOR)/TNPW(SOR)/DSR/Metro Water(SOR)/TNEB/Existing rates available in CMRL /Market Rate(Minimum three quotation if rate not available).	There is no Price Center ".1" available in tender documents. Kindly provide. Also please note that this is not an % above/ below type of tender wherein Bidder quotes +/-% on given rates, therefore SOR of TNPWD or CPWD shall not be applicable.	Refer addendum	Yes
210	1st Set Prebid Queries dated 5th January, 2016	NIT Item No. 10: Date and Time of Submission of Tender		04.02.2016 (upto 14:00 hrs) at Office of the Chief General Manager (UG-Construction), Address as mentioned in item no. 8 above.	Kindly extend the date of submission of tender as under: 04.03.2016 (upto 14:00 hrs) at Office of the Chief General Manager (UG-Construction), Address as mentioned in item no. 8 above.	Refer to Addendum	Yes

CONTRACT NO. PHASE-I EXTENSION
UAA-08 "Design Validation and Construction of works of underground station Boxes D-Wall at Sir Thiyagaraya College (CH:1016.000m) & Korrukupet (CH:2035.000m) Station, Including Associated Cut-Cover And Bored TBM Tunnels"

PREBID QUERIES

S.NO	Date of Query	Page/ Vol No	Clause No	As in Tender Document	Query	Response by CMRL	Addendum
211	2nd Set Prebid Queries dated 19th January, 2016	NIT Cl.3 Sec VIII Contract Data Sub Clause 1.14,3		Duration of Contract - 20 months from date of issue of LOA Time for completion - 720 days -. 24 months	Kindly confirm Time for completion.	Refer to Addendum	Yes
212	2nd Set Prebid Queries dated 19th January, 2016	NIT Clause 1		Design Validation and Construction of 2 Underground Station Boxes including associated Cut- Cover and Bored TBM Tunnels	Request to confirm scope under design validation.	Scope is already mentioned. Please refer to description of validation.	No
213	2nd Set Prebid Queries dated 19th January, 2016	ITB Cl.2		Source of funding —Clause deleted.	Kindly confirm financial closure & source of funding for the project	Refer to Addendum	Yes
214	2nd Set Prebid Queries dated 19th January, 2016	Bid Data Sheet ITB Cl.16.1(b), BDS-2		The period following completion of the Works during which spare parts, special tools etc. shall be available is Two Years.	Request to delete the clause since scope of work is only for civil works.	Agreed	Yes
215	2nd Set Prebid Queries dated 19th January, 2016	Section III EQC Initial filter, Clause 2.3 Note 1(ii), EQC 1Q		(ii) Auditor's Certificate has to be provided by the Bidder.	Kindly provide format for the Certificate to be submitted. Also confirm whether Certificate can be by any CA.	Agreed.	No
216	2nd Set Prebid Queries dated 19th January, 2016	Section IV - Bidding Forms, Schedule of Adjustment Data, Table A, BF-8		Bidder to propose weightages.	Bidder can fill table (Table-A) for each Schedule, separately. Kindly confirm.	Refer to Addendum	Yes
217	2nd Set Prebid Queries dated 19th January, 2016	Section IV - Bidding Forms, Preamble Clause 1.1.1, BF-10		These baseline quantities are as per tender design drawings. The positive or negative variations will be limited to these items only.	If there is a variation between Table-3 Baseline quantity. and tender drawing quantity for a particular item's, whether Contractor has to quote for Table-3 quantity only and actual quantity executed will be paid as per the rate quoted. Please clarify.	Refer to Addendum	Yes
218	2nd Set Prebid Queries dated 19th January, 2016	Section IV - Bidding Forms, Preamble Clause 1.1.1, BF-10		In case there is a change in tender design quantities in order to evaluate the variation amount a schedule of baseline quantities has been given for launching shaft, retrieval shaft, Sir Thiyagaraya station D-Wall, Korukkupet station D-Wall, First stage concrete in bored tunnel. These baseline quantities are as per tender design drawings. The positive or negative variations will be limited to these items only.	Request for provision of limit for variation upto +/- 10% of total Contract Value.	Not agreed	No
219	2nd Set Prebid Queries dated 19th January, 2016	Section IV Preamble Cl.1.1.2, BF- 10		In Sir Thiyagaraya station and Kurukkupet station maximum payment will be restricted to 90% of the total value of D-Wall construction. To verify the quality of construction to be as per contractual requirements 10% of the total value of works will be held with the Employer and will only be released once the excavation contractor had excavated the station.	Request for provision of submission of Bank Guarantee against cash retention.	Refer to Addendum	Yes
220	2nd Set Prebid Queries dated 19th January, 2016	Section IV Preamble Cl.1.3.3, BF- 13		Price Center J is dedicated to the costs relating to the confirmation of location, diversion, relocation, protection, support, etc. of the charted utilities as detailed in the Drawings in Volume 6, and any such works to be executed shall be on a resource measurement basis.	Price Centre "J" not available in the tender document. Request to kindly provide the same.	Refer to Addendum	Yes
221	2nd Set Prebid Queries dated 19th January, 2016	Section IV Preamble Cl.1.3.3, BF- 13		Price Center 1 is dedicated to the costs relating to the confirmation of location, diversion, relocation, protection, support, etc. of the charted utilities as detailed in the Drawings in Volume 6, and any such works to be executed shall be on a resource measurement basis.	All approvals / permissions required for utility shifting or diversion from relevant agencies shall be arranged by the Employer at Employer's cost. Please confirm. In case of any delay in getting permissions or approval Contractor shall be entitled for time and cost compensation.	Not agreed	No

CONTRACT NO. PHASE-I EXTENSION
UAA-08 "Design Validation and Construction of works of underground station Boxes D-Wall at Sir Thiyagaraya College (CH:1016.000m) & Korrukupet (CH:2035.000m) Station, Including Associated Cut-Cover And Bored TBM Tunnels"

PREBID QUERIES

S.NO	Date of Query	Page/ Vol No	Clause No	As in Tender Document	Query	Response by CMRL	Addendum
222	2nd Set Prebid Queries dated 19th January, 2016	Section IV - Bidding Forms, 1.7- Pricing Summary Note 5, BF-17		The Equivalent Total Amount shall be equal to the sum of the Tender Totals, minus the sum inserted for Basic Customs Duties.	Terms "Equivalent Total Amount" is not clear. Statement is also not clear. Please clarify.	Refer to Addendum	Yes
223	2nd Set Prebid Queries dated 19th January, 2016	Section IV - Bidding Forms Form FIR -2, BF-65		Note: Bidders should demonstrate sufficient available funds to meet the current contract commitments	Please let us know how Bidders are expected to demonstrate sufficient available funds to meet the current contract commitments	Pl read the contract condition	No
224	2nd Set Prebid Queries dated 19th January, 2016	Section IV - Bidding Forms Form FIR -2, BF-65			Kindly confirm whether Form FIR-2 is required to be certified by CA.	Yes.	No
225	2nd Set Prebid Queries dated 19th January, 2016	Section VII GCC Clause 4.1.2 Sec IV Bidding formsunforeseeable Table 2		As per GCC Clause - If and to the extent that the Contractor encounters physical conditions which are Unforeseeable, gives such a notice, and suffers delay and/or incurs Cost due to these conditions, the Contractor shall be entitled subject to notice under Sub-Clause 20.1 [Contractor's Claims] to: (a) an extension of time for any such delay, if completion is or will be delayed, under Sub-Clause 8.4 [Extension of Time for Completion], and (b) payment of any such Cost, which shall be included in the Contract Price As per Table 2 - Geotechnical Risk - Validation of Geotechnical profile and any unforeseen/ ground condition the tenderer should include this risk in his price	There is ambiguity between GCC clause and clause in Table 2. Kindly confirm that GCC clause shall be applicable.	Contract condition prevails.	No
226	2nd Set Prebid Queries dated 19th January, 2016	Section VII GCC Clause 1.0.2		The Engineer may, at the sole discretion of the Employer, issue a Taking-Over Certificate for any part of the Permanent Works.	If Taking Over Certificate is issued in parts, DLP for different parts of work shall start from date of issue of Taking Over Certificate for that part of work.	DLP starts from the date of Final taking over certificate.	No
227	2nd Set Prebid Queries dated 19th January, 2016	Section VII GCC Clause 14.7		Payment - The Employer shall pay to the Contractor: (b) the amount certified in each Interim Payment Certificate within 56 days after the Engineer receives the Statement and supporting documents	Request for Adhoc payment of 80% of each interim bill within 7 days of receipt of bill by the Employer and balance 20% within 15 days of submission of bill.	Not Agreed, However efforts will be made to release the payment as soon as possible in the interest of the work.	No
228	2nd Set Prebid Queries dated 19th January, 2016	Section VIII Table - Summary of Liquidated Damages as per Clause 8.7 of GC		-	In case the Contractor achieves subsequent keydate, the Liquidated damages levied on earlier keydate/s shall be refunded. Please confirm.	Not agreed	No

CONTRACT NO. PHASE-I EXTENSION
UAA-08 "Design Validation and Construction of works of underground station Boxes D-Wall at Sir Thiyagaraya College (CH:1016.000m) & Korrukupet (CH:2035.000m) Station, Including Associated Cut-Cover And Bored TBM Tunnels"

PREBID QUERIES

S.NO	Date of Query	Page/ Vol No	Clause No	As in Tender Document	Query	Response by CMRL	Addendum
229	2nd Set Prebid Queries dated 19th January, 2016	Section VIII Table - Summary of Liquidated Damages as per Clause 8.7 of GC			The delay of KDs have been divided into 3 categories i.e. 0-28, 29-56 & from 57 days. Please clarify: 1. Whether the amounts mentioned against the above categories for a delay in a particular KD shall apply on per day delay basis. OR The amount given shall be divided by the difference of upper and lower limit of days for a particular category, within which the delay of KD falls, and apply on no. of days of delay. 2. In case, there is a delay of 60 days for a particular KD, the applicable LD shall be the sum of LD amount mentioned in all the 3 categories or sum of first 2 categories upto 56 days and for balance 4 days (beyond 56 days) on prorata basis of the amount given in Cat-3. 3. Above clause can be interpreted in many manners, therefore request you to simplify it.	The clause is self explanatory	No
230	2nd Set Prebid Queries dated 19th January, 2016	Section VIII - Particular conditions Contract Data Sub-Clause 8.7		Maximum amount of delay damages - 10%	Kindly confirm maximum LD shall be 10% of total Contract Price or Balance value of work.	Maximum LD shall be 10% of contract Price	No
231	2nd Set Prebid Queries dated 19th January, 2016	Sec VIII Contract Data Sub Clause Cl.14.6 Sec IV Preamble Clause 1.5		Minimum Amount of Interim Payment Certificates — 2% of accepted contract amount Subject to the Tenderer's Monthly Statement meeting the minimum value of 1% of Contract Price, and after the Employer's Representative's assessment, the Employer's Representative will issue an Interim Payment Certificate calculated on percentages from the SOP Items	Kindly confirm minimum amount of interim payment certificate. In order to have a better cash flow to run the project smoothly, please remove provisions of minimum amount of interim payment certificate clause.	Refer addendum	Yes
232	2nd Set Prebid Queries dated 19th January, 2016	Section VIII - Specific Provision Clause SP 25, 2-17		In case of delay in handing over of the site by the Employer, the Contractor will be given extension of time only. The payment in the extended period in such cases will be with price adjustment effective from the original date of completion.	Request for provision of cost compensation along with extension of time, in case of delay in handing over of site by the Employer.	Not agreed	No
233	2nd Set Prebid Queries dated 19th January, 2016	Section VIII Specific Provision Clause SP 21 Sub Clause 13.7.2.5, 2-11		if the Price Variation Formula in SP Clause 22 below is adopted by the Contractor, then no addition or reduction in cost due to any Changes in Law will be allowed, except for changes to i) Customs Duties and ii) Excise Duties, iii) Output TN VAT which shall be to the Employer's account, to the extent that it is not covered by the Price Variation Formula	Request for provision for payment towards change in taxes or imposition of new taxes irrespective of Price variation clause.	Contract Condition prevails	No
234	2nd Set Prebid Queries dated 19th January, 2016	-		Plant advance	Request for interest free plant advance equal to 5% of Contract price.	Not agreed	No
235	2nd Set Prebid Queries dated 19th January, 2016	BF-71 (Form of Bid Security (Bank Guarantee))			As per the Gol guidelines, usage of Structured Financial Messaging System (SFIV15) for sending and receiving Inland Letters of Credit and Inland Bank Guarantees has been made mandatory for the Banks. Therefore, request you to provide following Banker details of CMRL: 1. Beneficiary Name: 2. Beneficiary Bank Name: 3. Bank Branch Address: 4. Account No.: 5. IFSC Code of the Branch:	1. Beneficiary Name: Chennai Metro rail Limited. 2. Beneficiary Bank Name: Corporation Bank 3. Bank Branch Address: Ashok Nagar, Chennai - 600083 4. Account No: CBCA01000531 5. IFSC Code of teh Branch: CORP0000578	No

CONTRACT NO. PHASE-I EXTENSION
UAA-08 "Design Validation and Construction of works of underground station Boxes D-Wall at Sir Thiyagaraya College (CH:1016.000m) & Korrukupet (CH:2035.000m) Station, Including Associated Cut-Cover And Bored TBM Tunnels"

PREBID QUERIES

S.NO	Date of Query	Page/ Vol No	Clause No	As in Tender Document	Query	Response by CMRL	Addendum
236	2nd Set Prebid Queries dated 19th January, 2016	Drg. No. DDC101-PD-TUN-ST-DW-13152	-		Please confirm if there is a requirement of any kind of treatment (soil stabilization) from ground level (road surface) of the cross passages passing below the roads.	Yes, refer to Addendum.	Yes
237	2nd Set Prebid Queries dated 19th January, 2016		-		At some of the locations, cross passages are very near to the buildings (for example - CP5). In case, soil stabilization treatment, if required to be done from top, Contractor shall not be able to deploy his machineries. Can the realignment be done in such cases. Please confirm	Not agreed	No
238	2nd Set Prebid Queries dated 19th January, 2016	Drg. No. DDC101-PD-TUN-GE- OW-13053	-		Please provide the traffic diversion plan for execution of D Wall of Korukkupet Station.	Refer to Addendum	Yes